

SIDEWALK SUB-SUMMARY

CALC. V.L.W.
BY DATE 5/22/95
CHKD. BY WDB
DATE 8/95

LAK - 615 - 2.82

OHIO
FHWA REGION 5

38
199

SIDEWALK SUB-SUMMARY								202		608	608		608	608	608	608
SHEET No.	REF.	STREET	CENTERLINE STATION TO STATION	SIDE	LENGTH X WIDTH	SUBTRACT FOR DRIVES	4" CONCRETE WALK AS PER PLAN	WALK REMOVED SQ.FT.		4" CONCRETE WALK SQ.FT.	4" CONCRETE WALK, AS PER PLAN SQ.FT.		CURB RAMP TYPE 1, AS PER PLAN EACH	CURB RAMP TYPE 2 EACH	CURB RAMP TYPE 1 SQ.FT.	WALKWAY, MISC. BRICK WALK SQ.FT.
58	SW-2	STATE ROUTE 84	123+97 TO 124+09	LT.	12x4.9			59		59						
58	SW-3	STATE ROUTE 84	124+57 TO 124+77	LT.	20x4.9			98		98						
65	SW-1	STATE ROUTE 84	159+50 TO 160+49	LT.	99x5					495						
66	SW-1	STATE ROUTE 615	6+70 TO 8+00	LT.	130x5	5x12				590						
67	SW-1	STATE ROUTE 615	8+00 TO 9+55	LT.	155x5					775				1		
67	SW-2	STATE ROUTE 615	9+57.50	RT.											87	
67	SW-3	STATE ROUTE 615	10+15 TO 10+64.60	LT.	69.5x6.5		69.5x1			382	70	1				
67	SW-4	STATE ROUTE 615	10+64.60 TO 12+00	LT.	135.4x5.5		135.4x1			609	135					
67	SW-5	STATE ROUTE 615	10+38 TO 10+70.50	RT.	35x6.5		35x1			193	35	1				
67	SW-6	STATE ROUTE 615	10+70.50 TO 12+00	RT.	129.5x5.5	4.5x33	129.5x1			434	130					
67	SW-7	STATE ROUTE 615	10+50	LT.	6x4											24
68	SW-1	STATE ROUTE 615	12+00 TO 16+00	LT.	400x5.5	4.5x92	400x1			1386	400					
68	SW-2	STATE ROUTE 615	13+76	LT.	4x3			12		12						
68	SW-3	STATE ROUTE 615	14+40	LT.	7x4			28		28						
68	SW-4	STATE ROUTE 615	12+00 TO 13+87	RT.	187x5.5	4.5x30	187x1			707	187					
68	SW-5	STATE ROUTE 615	13+53	RT.	7x4			28		28						
68	SW-6	STATE ROUTE 615	13+87 TO 14+23.65	RT.	55.5x7		55.5x1			333	56	1				
68	SW-7	STATE ROUTE 615	14+47.69 TO 14+83.16	RT.	57.2x7		32x1			368	32	1				
68	SW-8	STATE ROUTE 615	14+83.16 TO 16+00	RT.	116.8x5.5	4.5x15	116.8x1			458	117					
68	SW-9	STATE ROUTE 615	15+42	RT.	10x4			40		40						
69	SW-1	STATE ROUTE 615	16+00 TO 20+00	LT.	400x5.5	4.5x105	400x1			1328	400					
69	SW-2	STATE ROUTE 615	16+12	LT.	8x3			24		24						
69	SW-3	STATE ROUTE 615	16+86	LT.	6x3			18		18						
69	SW-4	STATE ROUTE 615	17+03	LT.	9x3			27		27						
69	SW-5	STATE ROUTE 615	19+51	LT.	11x5			55		55						
69	SW-6	STATE ROUTE 615	16+00 TO 17+15.93	RT.	115.9x5.5		115.9x1			522	116					
69	SW-7	STATE ROUTE 615	17+15.93 TO 17+41	RT.	29x8.0		29x1			203	29	1				
69	SW-8	STATE ROUTE 615	17+84 TO 18+10	RT.	30x8.0		30x1			210	30	1				
69	SW-9	STATE ROUTE 615	18+10 TO 20+00	RT.	190x5.5	4.5x15	190x1			788	190					
69	SW-10	STATE ROUTE 615	19+00	RT.	8x4			32		32						
70	SW-1	STATE ROUTE 615	20+00 TO 24+00	LT.	400x5.5	4.5x78	400x1			1449	400					
70	SW-2	STATE ROUTE 615	21+72	LT.	5x3			15		15						
70	SW-3	STATE ROUTE 615	22+45	LT.	12x4											48
70	SW-4	STATE ROUTE 615	20+00 TO 20+96.66	RT.	96.7x5.5	4.5x19	96.7x1			350	97					
70	SW-5	STATE ROUTE 615	20+96.66 TO 21+22.50	RT.	30x8.0		30x1			210	30	1				
70	SW-6	STATE ROUTE 615	21+65 TO 21+91.66	RT.	30x8.0		30x1			210	30	1				
70	SW-7	STATE ROUTE 615	21+91.66 TO 24+00	RT.	208.3x5.5	4.5x19	208.3x1			852	208					
70	SW-8	STATE ROUTE 615	23+69 TO 23+74	RT.	8x4			32		32						
SHEET TOTAL								468		13,288	2,724		8	1	87	72

FOR TYPICAL SECTIONS SEE SHEETS 4 THROUGH 10.

QUANTITIES CARRIED TO SHEET 39