SIDEWALK SUB-SUMMARY

CALC. BY W.W DATE 5/22/95
CHKD. BY WDS DATE 8/00

LAK - 615 - 2.82

OHIO
FHWA REGION 5

39
199

SIDEWALK SUB-SUMMARY

SHEET No.	REF.	STREET	CENTERLINE STATION TO STATION	SIDE	LENGTH X WIDTH	SUBTRACT FOR DRIVES	4" CONCRETE WALK AS PER PLAN	202 WALK REMOVED SQ.FT.	202 CONCRETE STEPS REMOVED LUMP	608 4" CONCRETE WALK SQ.FT.	608 4" CONCRETE WALK, AS PER PLAN SQ.FT.	608 CONCRETE STEPS, TYPE A WITH HANDRAIL LIN.FT.	608 CURB RAMP TYPE 1, AS PER PLAN EACH	608 CURB RAMP TYPE 2 EACH	608 CURB RAMP TYPE 1 SQ.FT.	608 WALKWAY, MISC: BRICK WALK SQ.FT.
71	SW-1	STATE ROUTE 615	24+00 TO 28+00	LT.	400x5.5	4.5x60	400x1			1530	400					
71	SW-2	STATE ROUTE 615	24+05	LT.	5x4			20		20						
71	SW-3	STATE ROUTE 615	26+47	LT.	6x4			24		24						
71	SW-4	STATE ROUTE 615	27+27	LT.	6x4			16	1	16		8				
71	SW-5	STATE ROUTE 615	24+00 TO 24+62.43	RT.	62.4x5.5		62.4x1			281	62					
71	SW-6	STATE ROUTE 615	24+62.43 TO 24+90	RT.	32x8.0		32x1			224	32		1			
71	SW-7	STATE ROUTE 615	25+36 TO 25+63.45	RT.	33x8.0		33x1			231	33		1			
71	SW-8	STATE ROUTE 615	25+63.45 TO 28+00	RT.	236.6x5.5	4.5x53	236.6x1			826	237					
71	SW-9	STATE ROUTE 615	26+38	RT.	6x4			24		24						
73	SW-1	STATE ROUTE 615	28+00 TO 31+00	LT.	300x5.5	4.5x67	300x1			1049	300					
73	SW-2	STATE ROUTE 615	28+60	LT.	6x3			18		18						
73	SW-3	STATE ROUTE 615	29+62	LT.	6x3.5			21		21						
73	SW-4	STATE ROUTE 615	28+00 to 31+00	RT.	300x5.5	4.5x48	300x1			1134	300					
75	SW-1	STATE ROUTE 615	31+00 TO 32+53.92	LT.	153.9x5.5	4.5x45	153.9x1			490	154					
75	SW-2	STATE ROUTE 615	32+53.92 TO 33+27.10	LT.	73.2x7	5x26	73.2x1			309	73					
75	SW-3	STATE ROUTE 615	33+27.10 TO 34+36	LT.	108.9x5					545						
75	SW-4	STATE ROUTE 615	31+00 TO 31+42	RT.	42x5.5		42x1			189	42					
75	SW-5	STATE ROUTE 615	31+42 TO 31+68	RT.	30x8		30x1			210	30		1			
75	SW-6	STATE ROUTE 615	32+09 TO 33+38.75	RT.	34x9		34x1			272	34		1			
75	SW-7	STATE ROUTE 615	33+38.75 TO 33+98.50	RT.	59.7x5	5x29				154						
75	SW-8	STATE ROUTE 615	32+59	RT.	5x2.5			13		13						
77	SW-1	SEATON PLACE	10+60 TO 11+13	RT.	53x5.5	4.5x15	53x1			171	53					
77	SW-2	SEATON PLACE	10+41 TO 11+06	LT.	65x5					325						
78	SW-1	HALLNORTH DRIVE	10+41 TO 11+20	LT.	79x5					395						
78	SW-2	HALLNORTH DRIVE	10+36 TO 11+20	RT.	84x5	5x18				330						
79	SW-1	GRENWAY DRIVE	10+37 TO 11+50	LT.	113x5	5x17				480						
79	SW-2	GRENWAY DRIVE	10+37 TO 11+50	RT.	113x5					565						
79	SW-3	GRENWAY DRIVE	11+04	RT.	3x4			12		12						
80	SW-1	FORESTVIEW DRIVE	10+40 TO 12+37	LT.	197x5	5x25				860						
80	SW-2	FORESTVIEW DRIVE	10+38 TO 12+40	RT.	202x5	5x37				825						
81	SW-1	ESTHER STREET	10+37 TO 11+45	LT.	108x5	5x18				450						
81	SW-2	ESTHER STREET	10+37 TO 11+68	RT.	131x5	5x17				570						
							SHEET TOTAL	148	1	12,563	1,750	8	4			
							SHEET 38 TOTAL	468		13,288	2,724		8	1	87	72
							GRAND TOTAL	616	1	25,851	4,474	8	12	1	87	72

FOR TYPICAL SECTIONS SEE SHEETS 4 THROUGH 10.

QUANTITIES CARRIED TO GENERAL SUMMARY

h:/ct/90272/cad/swsubsum - layer 2