ROADWAY SUB-SUMMARY

CALC. BY	VLW
DATE	3/28/95
CHKD. BY	WDB
DATE	4/5/95

LAK – 615 – 2.82

OHIO

FHWA REGION 5

45 / 199

ROADWAY SUB-SUMMARY		202	202	202	202	202	202	202		202		202		604	606	SPECIAL
SHEET NO.	STREET NAME	STRUCTURE REMOVED	WALK REMOVED	CURB REMOVED	GUARDRAIL REMOVED	PIPE REMOVED 24" AND UNDER	MANHOLE REMOVED	CATCH BASIN OR INLET REMOVED		FENCE REMOVED		REMOVAL MISC: COBBLESTONE PILLARS REMOVED & REPLACED		MONUMENT ASSEMBLY	GUARDRAIL TYPE 5	FILL AND PLUG EXISTING CONDUIT
		LUMP	S.F.	L.F.	L.F.	L.F.	EACH	EACH		L.F.		LUMP		EACH	L.F.	L.F.
58	S.R.84	LUMP			225										225	75
64	S.R.84	LUMP				10										
65	S.R.84	LUMP				137		2								
65A	GARFIELD ROAD															55
66	S.R.615		650													
67	S.R.615	LUMP	2590			50	2	4		284						
68	S.R.615	LUMP	3800	85		410	1	3		157				1		
69	S.R.615	LUMP	3858			285	2	1		12				2		
70	S.R.615	LUMP	3848			439	1	1						1		
71	S.R.615	LUMP	3840	10		469	3	1		99		LUMP		1		
73	S.R.615	LUMP	3000	31		300	1			54						
75	S.R.615	LUMP	1280	37		419	3	2						1		
77	SEATON PLACE		360	238		82	1	3		70						
78	HALLNORTH DRIVE		940			44										
79	GRENWAY DRIVE		1240			40										
80	FORESTVIEW AVENUE		2125	425		70		2		42						
81	ESTHER STREET	LUMP	1260			127				92						
TOTALS		LUMP	28791	826	225	2882	14	19		810		LUMP		6	225	130

QUANTITIES CARRIED TO THE GENERAL SUMMARY

SUBSUMMS.DWG – layer 0003