DRIVEWAY SUB-SUMMARY

FOR ADDITIONAL DRIVEWAY DETAILS
SEE SHEETS 150 & 151

STREET NAME	SHEET NUMBER	REFERENCE NUMBER	CENTERLINE STATION	SIDE	TYPE R or C	EXISTING RIGID DRIVEWAY AVG. WIDTH x LENGTH (FT)	202 PAVEMENT REMOVED SQ YDS	PROPOSED DRIVEWAY DIMENSIONS (FT): BOMANITE AREA WIDTH x LENGTH	APRON AREA AVG. WIDTH x LENGTH	DRIVEWAY THRU SIDEWALK AREA LENGTH x WIDTH	DRIVEWAY AREA LENGTH x WIDTH	DRIVEWAY EXTRA AREA	PROPOSED DRIVEWAY AREAS: TOTAL RIGID AREA SQ YDS	TOTAL FLEXIBLE OR STONE AREA SQ YDS	203 EXCAVATION 5" DEPTH CU YDS	203 EXCAVATION 6" DEPTH CU YDS	203 EXCAVATION 8" DEPTH CU YDS	301 4" BITUMINOUS AGGREGATE BASE, PG64-22 CU YDS	301 5" BITUMINOUS AGGREGATE BASE, PG64-22 CU YDS	304 8" AGGREGATE BASE, AS PER PLAN CU YDS	448 1" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 CU YDS	452 6" PLAIN CONCRETE PAVEMENT SQ YD	452 6" PLAIN CONCRETE PAVEMENT, AS PER PLAN SQ YD	452 8" PLAIN CONCRETE PAVEMENT SQ YD	452 8" PLAIN CONCRETE PAVEMENT, AS PER PLAN SQ YD
S.R.615	66	DR-1	7+92	LT.	R				15x10	5x12	2x11		23.3	2.4		3.9	0.5			0.5		23.3			
S.R.615	67	DR-1	11+02	RT.	R			20x1		4.5x18	7x12		9.0	9.3	1.3	1.8		1.0			0.3	9.0	2.2		
S.R.615	67	DR-2	11+59	RT.	R			18x1		4.5x15	14x15.5		7.5	24.1	3.3	1.5		2.7			0.7	7.5	2.0		
S.R.615	68	DR-1	12+00	LT.	R			18x1		4.5x15	5x12		7.5	6.7		1.5	1.5			1.5		7.5	2.0		
S.R.615	68	DR-2	12+21	LT.	R			18x1		4.5x15	6x12		7.5	8.0		1.5	1.8			1.8		7.5	2.0		
S.R.615	68	DR-3	12+35	RT.	R			18x1		4.5x15	15x12		7.5	20.0		1.5	4.4			4.4		7.5	2.0		
S.R.615	68	DR-4	13+07	LT.	R			18x1		4.5x16	5x13		7.5	7.2		1.6	1.6			1.6		8.0	2.0		
S.R.615	68	DR-5	13+20	RT.	R			18x1		4.5x15	9x12	4.4x9.5	7.5	16.6		1.5	3.7			3.7		7.5	2.0		
S.R.615	68	DR-6	13+67	LT.	R			18x1		4.5x16	4x13		8.0	5.8		1.6	1.3			1.3		8.0	2.0		
S.R.615	68	DR-7	14+27	LT.	R	10x4	4.4	18x1		4.5x15	10.8x12		21.9			4.0						21.9	2.0		
S.R.615	68	DR-8	15+41	LT.	R			18x1		4.5x15	11x11.5		7.5	14.1		1.5	3.1			3.1		7.5	2.0		
S.R.615	68	DR-9	15+76	RT.	R			18x1		4.5x15	6x12		7.5	8.0	1.1	1.5		0.9			0.2	7.5	2.0		
S.R.615	69	DR-1	16+65	LT.	R	17x24	45.3	20x1		4.5x19	15x16		38.7			6.8						38.7	2.2		
S.R.615	69	DR-2	16+80	LT.	R	9x24	24.0	15x1		4.5x14	9x13	3x19	26.3			5.1						29.0	1.7		
S.R.615	69	DR-3	17+42	LT.	R			18x1		4.5x14	8x10.5		7.0	9.3		1.4	2.1			2.1		7.0	2.0		
S.R.615	69	DR-4	18+39	LT.	R			18x1		4.5x14	15x11.5		7.0	19.2		1.4	4.3			4.3		7.0	2.0		
S.R.615	69	DR-5	18+72	RT.	R			18x1		4.5x15	14x11.5		7.5	17.9		1.5	4.0			4.0		7.5	2.0		
S.R.615	69	DR-6	18+98	LT.	R			18x1		4.5x14	15x10		7.0	16.7		1.4	3.7			3.7		7.0	2.0		
S.R.615	69	DR-7	19+67	LT.	R			18x1		4.5x15	11x12		7.5	14.7		1.5	3.2			3.2		7.5	2.0		
S.R.615	69	DR-8	19+90	LT.	R			18x1		4.5x15	8.5x12	2.5x9	7.5	13.8		1.5	3.1			3.1		7.5	2.0		
S.R.615	70	DR-1	20+13	RT.	R	16.8x18.5	34.6	21x1		4.5x19	7x16		21.9			4.0						21.9	2.3		
S.R.615	70	DR-2	20+53	LT.	R			18x1		4.5x14	3x11		7.0	3.7	0.5	1.4		0.4			0.1	7.0	2.0		
S.R.615	70	DR-3	21+44	LT.	R			18x1		4.5x15	3x12		7.5	4.0		1.5	0.9			0.9		7.5	2.0		
S.R.615	70	DR-4	22+33	LT.	R			18x1		4.5x14	17x11		7.0	20.8		1.4	4.6			4.6		7.0	2.0		
S.R.615	70	DR-5	23+57	LT.	R			18x1		4.5x15	5x12	6x11	7.5	14.0		1.5	3.1			3.1		7.5	2.0		
S.R.615	70	DR-6	23+83	RT.	R			21x1		4.5x19	11x16		9.5	19.6		1.9	4.3			4.3		9.5	2.3		
S.R.615	70	DR-7	23+85	LT.	R			22x1		4.5x20	11x17		10.0	20.8	2.9	2.0		2.3			0.6	10.0	2.4		
														TOTAL	9.1	57.7	51.2	7.3		51.2	1.9	304.3	53.1		
						TOTAL	167.3							SHEET TOTAL	118.0			7.3		51.2	1.9	304.3	53.1		

R = RESIDENTIAL DRIVEWAY
C = COMMERCIAL DRIVEWAY

SUBSUMMS.DWG - LAYER 008