



ITEM	QUANTITY	UNIT	LOCATION
FENCE REMOVED		L.F.	
MANHOLE REMOVED		EA.	
PIPE REMOVED 24" AND UNDER	300	L.F.	
CURB REMOVED		L.F.	
WALK REMOVED	1500	S.F.	
STRUCTURE REMOVED		LUMP	
TREE AND/OR STUMP REMOVED, 30" SIZE	1	EA.	
TREE AND/OR STUMP REMOVED, 18" SIZE	2	EA.	
TOTALS			

ITEM	QUANTITY	UNIT	LOCATION
MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN TYPE 1		EA.	
24" x 12" x 24" TEE		EA.	
MANHOLE, NO. 3, AS PER PLAN		EA.	
CATCH BASIN, NO. 3A, AS PER PLAN		EA.	
CATCH BASIN, NO. 3, AS PER PLAN		EA.	
24" CONDUIT, TYPE B AS PER PLAN, 706.02	100	L.F.	
12" CONDUIT, TYPE B AS PER PLAN, 706.02	48	L.F.	
TOTALS			

QUANTITIES HAVE BEEN CARRIED TO SUB-SUMMARY SHEETS 42-45

FOR STORM SEWER CONNECTION SCHEDULE SEE SHEET 46
 FOR SANITARY SEWER CONNECTION SCHEDULE SEE SHEET 47
 FOR TYPICAL SECTIONS SEE SHEETS 4-10
 FOR CROSS SECTIONS SEE SHEETS 116-117
 FOR UNDERDRAIN QUANTITIES SEE SHEETS 40-41
 FOR DRIVEWAY PROFILES SEE SHEETS 137-138
 FOR CATCH BASIN DETAILS SEE SHEETS 145-146
 FOR SANITARY SEWER DETAILS SEE SHEETS 147-148
 FOR ROADWAY DETAILS SEE SHEET 149
 FOR DRIVEWAY DETAILS SEE SHEETS 150-151
 FOR PAVEMENT MARKING PLANS SEE SHEET 161
 FOR SIGNING PLANS SEE SHEET 165

REF	LOCATION	QUANTITY	UNIT
D-1	STA. 28+00.00 RT. TO STA. 29+00.00 RT.		L.F.
D-2	STA. 28+00.00 LT. TO STA. 29+00.00 LT.		L.F.
D-3	STA. 29+00.00 LT.		L.F.
D-4	STA. 29+00.00 RT.		L.F.
D-5	STA. 29+00.00 RT. TO STA. 31+00.00 RT.		L.F.
D-6	STA. 29+00.00 LT. TO STA. 31+00.00 LT.		L.F.
D-7	STA. 30+30.00 RT.		L.F.
D-8	STA. 31+00.00 LT.		L.F.
S-1	STA. 28+38.17 RT.		EA.
S-2	STA. 30+78.08 RT.		EA.
TOTALS			