



QUANTITIES HAVE BEEN CARRIED
 TO SUB-SUMMARY SHEETS 42-45
 FOR TYPICAL SECTION SEE SHEET 4
 FOR CROSS SECTIONS SEE SHEET 96-99
 FOR CATCH BASIN DETAILS SEE SHEET 145-146
 FOR ROADWAY DETAILS SEE SHEET 149

[Hatched Box] EXISTING PAV'T TO BE REMOVED
 [Cross-hatched Box] DITCH EROSION PROTECTION

STA.	DESCRIPTION	EA.	L.F.	EA.	L.F.	EA.	L.F.	TOTALS
604	8" PLUG	EA.						1
604	MANHOLE NO. 4, AS PER PLAN	EA.						1
604	MANHOLE NO. 3, AS PER PLAN	EA.	1					1
604	CATCH BASIN NO. 4, WITH E GRATE, AS PER PLAN	EA.	1					1
603	60" CONDUIT, TYPE B AS PER PLAN (A) 706.02, 1500 D-LOAD	L.F.		130				130
603	54" CONDUIT, TYPE B, AS PER PLAN (A), 706.02	LUMP			270			270
603	15" CONDUIT, TYPE C AS PER PLAN, 706.02	EA.	1					1
TOTALS								

DRAINAGE AND SANITARY	LOCATION	L.F.	EA.	L.F.	EA.	L.F.	TOTALS	
							LUMP	EA.
DRAINAGE AND SANITARY	D-1 STA. 154+00.00 RT. TO STA. 155+30.00 RT.							
	D-2 STA. 155+30.00 RT.							
	D-3 STA. 155+30.00 RT. TO STA. 158+00.00 RT.							

STA.	ELEVATION	CONDUIT		PROFILES
		TYPE	SIZE	
725	725			
720	720			
715	715			
710	710			
705	705			
700	700			
695	695			
690	690	130'-	60" CONDUIT TYPE B @ 0.49%	
685	685	270'-	64" CONDUIT TYPE B @ 0.49%	
680	680			
675	675			

STA.	DESCRIPTION	EA.	L.F.	EA.	L.F.	TOTALS
202	PIPE REMOVED 24" AND UNDER	L.F.	10			10
202	STRUCTURE REMOVED	LUMP				1
201	TREE AND/OR STUMP REMOVED, 18" SIZE	EA.	1			1
TOTALS						

CHANGE ORDER
 184-01
 9-5-01 8/8

ROADWAY	LOCATION	L.F.	EA.	L.F.	EA.	L.F.	TOTALS	
							LUMP	EA.
ROADWAY	R-1 STA. 155+29.00 RT.							
	R-2 STA. 156+90.00 RT.							