

GENERAL NOTES

ITEM SPECIAL - REMOVAL AND DISPOSAL OF EXISTING UNDERGROUND STORAGE TANKS

This item shall include the removal, backfilling, and disposal of underground storage tanks as designated in the plans. The tanks shall be completely removed, shall become the property of the Contractor, and shall be disposed of by him. The backfilling and compacting of the excavated area shall be done in accordance with the provisions of Item 203.

This item shall be paid for at the unit price bid for each "Item Special - Removal and Disposal of Existing Underground Storage Tanks," which price and payment shall be full compensation for removing and disposing of excess materials, backfilling, and all labor, tools, equipment and incidentals necessary to complete this item, including incidental excavation.

SEEDING

Quantities for seeding are calculated for the soil areas between the right-of-way lines or within the work limits for areas outside the right-of-way lines covered by temporary easements.

AGRICULTURAL LIMING MATERIALS

The location and need for agricultural liming materials will be determined by laboratory tests after rough grading operations have been performed. Quantities of agricultural liming material, as shown on the plans, are sufficient for the entire project, but will be non-performed for the areas where tests show that the liming material is not needed. Where used the rate of application shall conform with 659.08 of the specifications.

DUST CONTROL

A quantity of calcium chloride and water is provided for use for dust control as directed by the Engineer:

Item 616	Calcium Chloride	10 tons
Item 616	Water	250 M. Gal.

MAINTENANCE OF TRAFFIC ITEMS

Local traffic shall be maintained in accordance with 614.02 (a) of the specifications. The following items have been included in the general summary for use as directed by the Engineer:

Item 404	Asphalt Concrete or an Approved Bituminous Pre-Mixed Surface Course for Maintaining Traffic	100 c.y.
Item 410	Traffic Compacted Surface, Type A or B	2,000 c.y.
Item 410	Traffic Compacted Surface, Type C	1,000 c.y.
Item 616	Calcium Chloride	85 tons

CONNECTIONS TO EXISTING PIPE

At places where the plans provide for proposed pipe to be connected to existing pipe, it shall be the responsibility of the Contractor to locate the existing pipe both as to line and grade before he starts to lay the proposed pipe. The cost of this operation shall be included in the unit price bid for the pertinent 603 conduit item.

MAINTENANCE OF SEWER FLOWS

The Contractor shall conduct his operations so as to maintain at all times sewer flows through existing facilities to remain in place and through existing facilities to be replaced until new facilities are completed and placed into use.

Payment for any additional costs involved in maintaining these flows by pumping or by any other means approved by the Engineer shall be included in the unit prices bid for the respective items of 603 conduit.

REPLACEMENT OF EXISTING SANITARY SERVICES

Existing sanitary services, which are connected to a user and which are disturbed because of this project, shall be replaced by the Contractor.

If the sewer is to be abandoned, service connections shall be provided to the relocated sewer in accordance with the detail shown on Sheet 51.

The following estimated quantities have been included in the General Summary, for use as directed by the Engineer, to perform the work noted above.

Item 603	6" Conduit, Type B 706.08, with joints. as per 706.12	200 l.f.
----------	---	----------

Payment for all necessary bends or branches shall be included in the unit price bid for the pertinent conduit item.

EXTENSION OF EXISTING SANITARY SERVICES

Existing sanitary services, which are not connected to a user and which terminate beneath the proposed pavement and sidewalk, shall be extended to the right-of-way line, in accordance with the detail shown on Sheet 51.

The locations of the unconnected services are shown in tabular form on Sheet 51, and were obtained from the records of the Lake County Sanitary Engineer.

The following estimated quantity has been included in the General Summary for the work noted above:

Item 603	6" Conduit, Type B 706.08, with joints. as per 706.12	1,800 l.f.
----------	---	------------

Payment for all necessary bends or branches shall be included in the unit price bid for the pertinent conduit item.

The Contractor shall record the locations of the extended services and shall furnish a list of the locations to the City.

NOTIFICATION

The Contractor shall notify the County Sanitary Engineer two days prior to starting work on the sanitary sewers or services.

DEC 11 1970

GENERAL NOTES