FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

12
181

LAKE COUNTY
LAK-615-3.26

GENERAL SUMMARY

TYPE CODE 7221

ITEM	SHEET NUMBER 5	7	14	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	R/W	ITEM	100% CITY PARTICIPATION	CITY, STATE, & FEDERAL PARTICIPATION		TOTAL	UNIT	DESCRIPTION
																														PAVEMENT
301				151			29		32				10					8	62	65				301		357		357	C.Y.	Bituminous Aggregate Base: 702.01 (85-100 or AC 10); or 702.09, RT-11 or RT-12
304				448		38	145	24	100	33	49		370		2	42	36	40	202	230		4		304		1757		1757	C.Y.	Aggregate Base
310											425	379	60	585	661	740	614	506			289	102		310		4301		4301	C.Y.	Subbase, Grading A, as per plan
402		100	239	62			12		13				4					3	26	27				402		486		486	C.Y.	Asphalt Concrete (70-85 or AC 20)
404			158	67		6	29	5	17		1		4			6	10	9	29	41		1		404		383		383	C.Y.	Asphalt Concrete (70-85 or AC 20)
408				752			150		161				53					40	309	319				408		1,784		1,784	Gal.	Bituminous Prime Coat, 702.09 RT-2 or RT-3
451				1,137	4,804	3,520	2,539	3,400	2,507	3,258	3,400	1,972		3,139	3,031	4,068	3,500	2,880	2,981	3,072		578		451		49,786		49,786	S.Y.	9" Reinforced Portland Cement Concrete Pavement
452				118	179	545	178	353	39	182	303		715		1043	134	139	102	217	236	3,180	90		452		8353		8353	S.Y.	7" Plain Portland Cement Concrete Pavement
609				347	986	1,140	717	1,164	715	1,132	1,440	743	462	1,133	1,351	1,104	952	709	824	888	1,514	200		609		17,521		17,521	L.F.	Concrete Curb, Standard Type 2A
611												172		170										611		342		342	S.Y.	Reinforced Concrete Approach Slabs (T-13")
407			568																					407		568		568	Gal.	Tack Coat, 702.04, MS-2 or RS-1; or 702.02, RC-70 or RC-250
411			214																					411		214		214	C.Y.	Stabilized Crushed Aggregate
																														EXISTING BUILDINGS REMOVED
202																							Lump	202		Lump		Lump	Lump	Parcel No. 10-WD, Removal of loading dock, roof overhang.
202																							Lump	202		Lump		Lump	Lump	Parcel No. 14-T, Removal of 1-story masonry service station.
202																							Lump	202		Lump		Lump	Lump	Parcel No. 41-T Removal of 1½ story frome residence.
202																							Lump	202		Lump		Lump	Lump	Parcel No. 90-WD, Removal of 1 story masonry commercial building.
202																							Lump	202		Lump		Lump	Lump	Parcel No. 97-WD, Removal of 1-story masonry commercial building.
202																														
202																							Lump	202		Lump		Lump	Lump	Parcel No. 109-WD, Removal of 1½ story frome residence.
																														LIGHTING
																														For Quantities See Sheet 75
																														RETAINING WALLS
																														Retaining Wall A For Quantities See Sheet 117
																														Retaining Wall B For Quantities See Sheet 122
																														STRUCTURES OVER 20 FOOT SPAN
																														LAK-615-0402 For Quantities See Sheet 133
614		Lump																						614	Lump	Lump		Lump	Lump	Maintaining Traffic
619	Lump																							619	Lump	Lump		Lump	Lump	Field Office
	Lump																								Lump	Lump		Lump	Lump	Construction Layout Stakes

GENERAL SUMMARY

ALL-STATE BLUEPRINT #40008

DEC 11 1970 JUN 26 1970