



PILING are 12" Cast-in-place reinforced concrete piles, estimated average pay length 25 ft. Steel sheet piling as shown on plans.

DIMENSIONS shown are measured horizontally.

SHEET PILING shall be driven to the lengths as shown in sheet 57B.

BURGESS & NIPLE LIMITED — CONSULTING ENGINEERS
COLUMBUS, OHIO

RETAINING WALL "B"
GENERAL PLAN AND ELEVATION - PILING PLAN

LAKE COUNTY STA. 42+60.00 STA. 47+02.79

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED DATE	REVISED
	K.E.D.	K.E.D.	J.E.C.	NOV 11-19-68	

DEC 11 1970 JUN 26 1970