CALC. BY _____ DATE 4-13-99
CHKD. BY _____ DATE 4/99

LAK – 615 – 4.64
LAK – VAR

OHIO
FHWA REGION 5

20
198

PAVEMENT SUB–SUMMARY
(CITY OF MENTOR–ON–THE–LAKE)

PAVEMENT SUB–SUMMARY TOTALS CARRIED TO GENERAL SUMMARY

PAVEMENT																						RESURFACING PROGRAM			
SHEET	STREET	202 PAVEMENT REMOVED SQ.YD.	203 SPECIAL – SOIL STERILANT SQ.YD.	203 EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION CU.YD.	203 SUBGRADE COMPACTION SQ.YD.	253 PAVEMENT REPAIR SQ.YD.	255 FULL DEPTH PAVEMENT SAW CUT LIN.FT.	301 6" BITUMINOUS AGGREGATE BASE, PG64–22 CU.YD.	301 8 3/4" BITUMINOUS AGGREGATE BASE, PG64–22 CU.YD.	304 4" AGGREGATE BASE, AS PER PLAN CU.YD.	304 6" AGGREGATE BASE, AS PER PLAN CU.YD.	407 TACK COAT (@ 0.10 GAL./SQ.YD.) GAL.	407 TACK COAT FOR INTERMEDIATE COURSE (@ 0.10 GAL./SQ.YD.) GAL.	408 BITUMINOUS PRIME COAT (@ 0.40 GAL./SQ.YD.) GAL.	448 1 1/4" ASPH. CONC. SURFACE COURSE, TYPE 1, PG64–22 CU.YD.	448 1 3/4" ASPH. CONC. INTERMEDIATE COURSE, TYPE 1, PG64–22 CU.YD.	451 9" REINFORCED CONCRETE PAVEMENT CU.YD.	452 10" PLAIN CONCRETE PAVEMENT SQ.YD.	830 CURB, TYPE 2–A, AS PER PLAN LIN.FT.	830 CURB, TYPE 3 LIN.FT.	830 CURB, TYPE 6 LIN.FT.	830 CURB, TYPE 6, AS PER PLAN LIN.FT.			254 PAVEMENT PLANING, BITUMINOUS SQ.YD.	407 TACK COAT (@ 0.10 GAL./SQ.YD.) GAL.	448 1/2" AVG. ASPH. CONC. INTERMEDIATE COURSE, TYPE 2, PG64–22 CU.YD.	448 1 1/4" ASPH. CONC. SURFACE COURSE, TYPE 1, PG64–22 CU.YD.
30	MUNSON ROAD			16.0	36.1				8.8		6.0	3.6		14.4	1.3							58.0				432	43.2	6.0	15.0
31	MUNSON ROAD			124.3	270.7			2.0	65.8		45.2	27.0		108.2	9.4							256.0				745	74.5	10.3	25.9
32	MUNSON ROAD			99.2	204.6			8.2	49.7		34.1	20.4		81.6	7.1											569	56.9	7.9	19.7
33	MUNSON ROAD			122.4	266.7			3.9	64.8		44.4	26.7		106.8	9.3											489	48.9	6.8	17.0
34	MUNSON ROAD			69.4	142.7			6.2	34.7		23.8	14.3		57.1	5.0											262	26.2	3.6	9.1
TOTAL		–	–	432	921	–	–	244		–	154	92	–	368	32	–	–	–	–	–	314	–			2497	250	35	87

COPYRIGHT 11-25-98 N:\CIVIL\CAD\MENTOR\SHEETS\SHEET.DWG PLOT: 1"=20'