DRIVEWAY SUB–SUMMARY

DRIVEWAY SCHEDULE

SHEET NO.	REF NO.	LOCATION (STA., LT. or RT.)	DRIVE TYPE	W1 LIN. FT.	W2 LIN. FT.	L APRON LIN. FT.	APRON AREA SQ. FT.	SIDEWALK AREA SQ. FT.	EXTRA AREA SQ. FT.	TOTAL AREA SQ. FT.	ITEM 202 PAVEMENT REMOVED SQ. YD.	ITEM 203 EXCAVATION 8" DEPTH CU. YD.	ITEM 203 EXCAVATION 11" DEPTH CU. YD.	ITEM 304 6" AGGREGATE BASE, AS PER PLAN CU. YD.	ITEM 304 8" AGGREGATE BASE AS PER PLAN CU. YD.	ITEM 448 1-3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 PG64-22 (DRIVEWAYS) CU. YD.	ITEM 448 1-1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS) CU. YD.	ITEM 448 2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS) CU. YD.	ITEM 408 BITUMINOUS PRIME COAT (@ 0.40 GAL./S.Y.) GAL.	ITEM 452 6" PLAIN CONCRETE PAVEMENT, CLASS MS SQ. YD.	ITEM 452 8" PLAIN CONCRETE PAVEMENT, CLASS MS SQ. YD.
141	DR–1	17+04.0, LT.	B	24.1	22.1	2.5	57.8		721.7	779.5		19.2		14.4				4.8	34.6		
142	DR–1	18+02.0, LT.	B	18.0	17.0	2.5	43.8		587.6	631.4		15.6		11.7				3.9	28.1		
142	DR–2	18+44.5, LT.	B	24.7	23.5	2.5	60.2		637.2	697.4		17.2		12.9				4.3	31.0		
142	DR–3	19+94.0, LT.	B	27.3	25.3	2.5	65.8		129.8	195.6		4.8		3.6				1.2	8.7		
142	DR–4	21+34.0, LT.	A	19.1	17.9	2.5	46.3		183.0	229.3	47.0			0.9				0.3	2.1	20.3	
143	DR–1	22+25.0, LT.	A	28.6	26.2	2.5	68.5		232.5	301.0	65.8	1.7		1.3				0.4	3.0	25.8	
143	DR–2	23+48.0, LT.	A	28.0	18.0	12.5	287.5		252.0	539.5	67.2									59.9	
144	DR–1	27+32.0, LT.	B	29.6	27.4	2.5	71.2		267.1	338.3		8.4		6.3				2.1	15.0		
144	DR–2	28+24.5, LT.	B	32.0	28.0	2.5	75.0		146.2	221.2		5.5		4.1				1.4	9.8		
144	DR–3	29+32.0, LT.	A	22.3	21.0	2.5	54.1		247.5	301.6	61.4			1.0				0.3	2.4	27.5	
144	DR–4	28+73.5, RT.	D	48.0	25.8	15.0	553.5		335.3	888.8			38.2		21.9	4.8	3.4		39.5		
144	DR–5	29+83.0, RT.	D	42.5	22.2	15.0	485.3		310.8	796.1			10.6		18.7	4.3	3.1		35.4		
145	DR–1	31+58.0, RT.	B	27.0	22.5	5.0	123.8		129.4	253.2		6.3		4.7				1.6	11.3		
145	DR–2	33+10.4, RT.	B	27.0	22.5	5.0	123.8		138.0	261.8		6.5		4.8				1.6	11.6		
146	DR–1	34+08.7, RT.	B	27.0	22.5	5.0	123.8		130.1	253.9		6.3		4.7				1.6	11.3		
146	DR–2	35+42.3, RT.	B	24.0	20.4	5.0	111.0		175.6	286.6		7.1		5.3				1.8	12.7		
146	DR–3	36+38.0, RT.	A	23.0	19.7	5.0	106.8		149.4	256.2	41.5			2.0				0.7	4.7	16.6	
SHEET TOTALS											282.9	98.6	40.8	77.7	41.6	9.1	6.5	26.0	261.2	150.1	
GRAND TOTALS											283.0	140.0		120.0		10.0	33.0		262.0	151.0	

NOTE:

(1) PAVEMENT REMOVED (ITEM 202) INCLUDES AREA WITHIN BIKE PATH.

(2) ALL DRIVE APRONS ALONG HENDRICKS ROAD SHALL BE ASPHALT, WITH THE EXCEPTION OF THE DRIVEWAY AT STA. 23+48, LT., WHICH WILL BE CONCRETE.

(3) THE MATERIAL TO BE USED FOR DRIVE AREAS BEYOND THE BIKEPATH SHALL BE ASPHALT FOR EXISTING GRAVEL OR ASPHALT DRIVES.

(4) SEE DRIVE PROFILES AND CROSS SECTIONS FOR LIMITS OF DRIVES.

H:\CT\93535\CAD\HENDRICK\DRIVESUM1.DWG Scale: 1"=20'

HENDRICKS ROAD DRIVEWAY SUB–SUMMARY