



FOR TYPICAL SECTIONS SEE SHEET 13  
 FOR CROSS-SECTIONS SEE SHEETS 149 THRU 165  
 FOR DRIVEWAY SCHEDULE & DETAILS SEE SHEET 24  
 FOR DRIVEWAY PROFILES SEE SHEET 166  
 FOR PAVEMENT DETAILS SEE SHEET 171  
 FOR TRAFFIC CONTROL DETAILS SEE SHEETS 172 THRU 198  
 FOR MAINTENANCE OF TRAFFIC DETAILS SEE SHEETS 17 & 18

ITEM	DESCRIPTION	QTY	UNIT	TOTAL
830	CURB, TYPE 3	450	LN.FT.	450
448	1-1/4" ASPH. CONC. SURFACE COURSE TYPE 1, PG64-22	17.4	CU.YD.	17.4
448	1-3/4" ASPH. CONC. INTERMEDIATE COURSE TYPE 2, PG64-22	24.3	CU.YD.	24.3
408	BITUMINOUS PRIME COAT (0.40 GAL./SQ.YD.)	200	GAL.	200
407	TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL./SQ.YD.)	25.0	GAL.	25.0
304	6" AGGREGATE BASE, AS PER PLAN	83.3	CU.YD.	83.3
203	SUBGRADE COMPACTION	500	SQ.YD.	500
SPEC.	SOIL STERILANT	500	SQ.YD.	500

PAVEMENT	LOCATION	TOTALS
REF	STA. 38+00 TO 42+50, RT. = 4500 S.F.	
P-1		

PROPOSED PROFILE GRADES 16.0' RT. 6.30	38+00	39+00	40+00	41+00	42+00	630
625						625
620	+0.10%	+0.64%	+0.08%	+0.54%	+0.86%	620
615						615
610						610
605						605
600						600
595						595

ROADWAY					
REF	LOCATION	LN.FT.	LN.FT.	EACH	EACH
R-1	STA. 38+00 TO STA. 38+23, RT.	23			
R-2	STA. 38+00 TO STA. 39+25, RT.		8	1	100
R-3	STA. 41+32.8, 17.3' RT. TO 25.2' RT.				
TOTALS					
		23	8	1	100

DRAINAGE & SANITARY					
REF	LOCATION	CU.YD.	LN.FT.	EACH	EACH
D-1	STA. 39+67.03, 45' RT. TO STA. 39+77.12, 33.53' RT.	0.84	15	1	
D-2	STA. 39+77.12, 33.53' RT. TO STA. 41+33, 27.5' RT.		156		1
D-3	STA. 41+32.8, 27.5' RT. TO STA. 42+50, 26.5' RT.		117		
TOTALS					
		0.84	273	15	1

H:\CT\92535\CAD\HENDRICK\HENRPPB.DWG 1"=20'

HENDRICKS ROAD PLAN & PROFILE STA. 38+00 TO STA. 42+50