

GENERAL SUMMARY

ITEM	SHEET NUMBER										ITEM	TOTAL	UNIT	DESCRIPTION		
	10	9	8	7	6	5	4	3	2	1						
														- ROADWAY -		
											LUMP	201	LUMP		CLERRING & GRUBBING	
												202	108	LIN. FT.	CURB REMOVAL	
	620	243	79	98	201	384						203	1625	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
	1048	187	167	29	26	38						203	1495	CU. YD.	EMBANKMENT	
	1152	1272	1200	1104	888	1056						203	6672	SG. YD.	SUBGRADE COMPACTION	
												606	2	EACH	GUARD POST, AS PER PLAN	
												608	11	EACH	BIKE RAMP, AS PER PLAN	
											50	616	50	M-GAL.	WATER	
															- PAVEMENT -	
												301	556	CU. YD.	BITUMINOUS AGGREGATE BASE; AC-20, RT-11 OR RT-12	
	96	106	100	92	74	88						404	279	CU. YD.	ASPHALT CONCRETE; AC-20	
	49	53	50	46	37	44										
															- TRAFFIC CONTROL -	
											1.12	621	1.12	MILE	CENTER LINES	
	130	182	78	52	52	143						630	637	LIN. FT.	GROUND MOUNTED SUPPORTS NO. 2 POST	
	42	46	30	9	17	50						630	194	SG. FT.	SIGNS, FLAT SHEET	
															- DRAINAGE -	
												604	2	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	
												603	35	LIN. FT.	12" CONDUIT, TYPE 'C'	
												603	60	LIN. FT.	12" CONDUIT, TYPE 'D'	
												603	8	LIN. FT.	12 x 4' REINFORCED CONCRETE BOX SECTION (AS PER SS 959) C-789	
															TABLE 3, DESIGN EARTH COVER 2', AS PER PLAN	
												604	1	EACH	CATCH BASIN STANDARD No. CB 2-2-A	
											2	604	2	EACH	MANHOLE FRAME & COVER, AS PER PLAN	
											2	604	2	EACH	CATCH BASIN FRAME & COVER, AS PER PLAN	
															- EROSION CONTROL -	
											2500	207	2500	SG. YD.	TEMPORARY SEEDING & MULCHING	
												207	50	EACH	STRAW OR HAY BALES	
											200	659	13338	SG. YD.	SEEDING & MULCHING	
												659	1.2	TON	COMMERCIAL FERTILIZER	
												659	5.6	TON	AGRICULTURAL LIMING	
											5.6	659	30	M. GAL.	WATER	
											30	659	650	SG. YD.	REPAIR SEEDING & MULCHING	
											650	SPEL.	6672	SG. YD.	HERBICIDE FOR WEED CONTROL	
	1152	1272	1200	1104	888	1056										
															- MISCELLANEOUS -	
											LUMP	619	LUMP		FIELD OFFICE	
												623	LUMP		CONSTRUCTION LAYOUT STAKES	
												624	LUMP		MOBILIZATION	

CENTER BIKE PATH