

FOR TYPICAL SECTIONS SEE SHEETS 6 THRU 15

PAVEMENT							203	304	305	407	446	446	451
STREET NAME	STATION TO STATION	LENGTH (FEET)	PAVEMENT AREA		BASE		SUBGRADE COMPACTION	6" AGGREGATE BASE, AS PER PLAN	10" CONCRETE BASE	TACK COAT 0.1 GAL/SQ YD	1 3/4" ASPH. CONCRETE INTERMEDIATE COURSE	1 1/2" ASPH. CONCRETE SURFACE COURSE AS PER PLAN	9" REINFORCED CONCRETE PAVEMENT
			AVE. WIDTH (FEET)	P'MT AREA SQ. YDS.	AVE. WIDTH (FEET)	P'MT AREA SQ. YDS.							
SR 615	55+25.00 - 56+00.00	75	63	525.0	65	541.7	541.7	90.3					525.0
SR 615	56+00.00 - 71+55.00	1555	54	9330.0	57	9848.3	9848.3	1641.4					9330.0
SR 615	71+55.00 - 76+32.57	477.57	63	3343.0	65	3449.1	3449.1	574.9					3343.0
EXTRA AREA SR 615 / SR 84	76+32.57 - 77+76.45			*1746.6		*1820.6	1820.6	303.4					1746.6
RAMP A	89+90.81 - 100+50.00	1059.51	26	3060.8	28	3296.3	3296.3	550.5					3060.8
RAMP A	100+50.00 - 101+00.00	50	27	150.0	29	161.1	161.1	26.9					150.0
RAMP A	101+00.00 - 109+07.02	807		*1898.1		*1942.9	1942.9	323.8	*1920.5	189.8	92.2	79.1	
RAMP B	60+31.98 - 77+69.41	1737.43		*3987.3		*4083.8	4083.8	682.0	*4035.6	398.7	193.8	166.1	
RAMP B	77+69.41 - 83+49.99	580.58	26	1677.2	26.5	1709.5	1709.5	284.9					1677.2
RAMP B	83+49.99 - 90+56.19	706.20	26	2040.1	27	2118.6	2118.6	353.1					2040.1
RAMP C	70+00.00 - 78+00.00	800		*2181.0		*2225.4	2225.4	370.9	*2203.2	218.1	106.0	90.9	
RAMP C	78+00.00 - 78+50.00	50	27	150.0	28	155.6	155.6	25.9					150.0
RAMP C	78+50.00 - 82+41.34	391.3	26	1130.5	27	1173.9	1173.9	195.7					1130.5
RAMP C	82+41.34 - 85+72.70	331.36	30	1104.5	31	1141.4	1141.4	190.3					1104.5
RAMP C	85+72.70 - 88+33.04	260.34	34	983.5	35	1012.4	1012.4	168.7					983.5
RAMP D	89+90.94 - 98+06.96	816.02	26	2357.4	27	2448.1	2448.1	408.0					2357.4
RAMP D	98+06.96 - 115+07.02	1700		*4765.0		*4859.4	4859.4	826.1	*4780.7	476.5	231.6	198.5	
							41989	7017	12940	1283	624	535	27599

QUANTITIES CARRIED TO GENERAL SUMMARY

* AREA CALCULATED BY COMPUTER

COPYRIGHT - DATE: 08-09-01 11:03 - CT CONSULTANTS, INC. H:\CT\97125\SDSK\pavesbsum.dwg

CALCULATED
J.M.Z.
CHECKED
W.B.B.

PAVEMENT SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

52
393