FOR TYPICAL SECTIONS SEE SHEETS 6 THRU 15

PAVEMENT							203	254	301	304	407	446	446		
STREET NAME	STATION TO STATION	LENGTH (FEET)	RESURFACE AREA AVE.WIDTH (FEET)	RESURFACE AREA P'MT AREA SQ. YDS.	PAVEMENT AREA AVE.WIDTH (FEET)	PAVEMENT AREA P'MT AREA SQ. YDS.	SUBGRADE COMPACTION SQ. YD.	1 1/4" PAVEMENT PLANING, BITUMINOUS SQ. YD.	8" BITUMINOUS AGGREGATE BASE CU.YDS.	3" AGGREGATE BASE AS PER PLAN CU.YDS.	TACK COAT 0.1 GAL./SQ. YD. GAL.	1 3/4" ASPH. CONCRETE INTERMEDIATE COURSE AS PER PLAN CU.YDS.	1 1/2" ASPH. CONCRETE SURFACE COURSE AS PER PLAN CU.YDS.		
SR 84	152+60.00 – 155+00.00	240		*782.1	13	346.7	346.7	782.1	77.0	28.9	78.2	16.9	47.0		
SR 84	155+00.00 – 160+09.00	509		*852.9	17	961.4	961.4	852.9	213.6	80.1	85.3	46.7	75.6		
SR 84	160+09.00 – 160+25.00	16		*29.0		*26.7	26.7	29.0	5.9	2.2	2.9	1.3	2.3		
SR 84	161+95.25 – 162+20.29			*87.6		*44.6	44.6	87.6	9.9	3.7	8.8	2.2	5.5		
SR 84	162+20.29 – 166+80.00	459.71		*1362.7		*937.4	937.4	1362.7	208.3	78.1	136.3	45.6	95.9		
SR 84	166+80.00 – 169+30.00	250	26.5	736.1		*417.2	417.2	736.1	92.7	34.8	73.6	20.3	48.1		
							2734	3851	608	228	385	133	275		

QUANTITIES CARRIED TO GENERAL SUMMARY

* AREA CALCULATED BY COMPUTER

CALCULATED JMZ | CHECKED WDB

PAVEMENT SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

53
393

COPYRIGHT – DATE: 08-09-01 11:03 , CT CONSULTANTS, INC. H:\CT\97125\SDSK\pavesbsum.dwg