FOR TYPICAL SECTIONS SEE SHEETS 6 THRU 15

PAVEMENT							203	254	301	304	407	407	411	446	446
			PAVEMENT AREA		BASE		SUBGRADE COMPACTION	3" PAVEMENT PLANING, BITUMINOUS	6" BITUMINOUS AGGREGATE BASE	6" AGGREGATE BASE, AS PER PLAN	TACK COAT 0.1 GAL/SQ.YD.	TACK COAT FOR INTERMEDIATE COURSE 0.05 GAL/SQ.YD	4" STABILIZED CRUSHED AGGREGATE	1 3/4" ASPH. CONCRETE INTERMEDIATE COURSE	1 1/4" ASPH. CONCRETE SURFACE COURSE AS PER PLAN
STREET NAME	STATION TO STATION	LENGTH (FEET)	AVE. WIDTH (FEET)	P'MT AREA SQ. YDS.	AVE. WIDTH (FEET)	P'MT AREA SQ. YDS.	SQ. YD.	SQ. YD.	CU.YDS.	CU.YDS.	GAL.	GAL.	CU.YDS.	CU.YDS.	CU.YDS.
MENTOR HILLS DRIVE	3+25.32 – 5+06.42	181.10	20	402.4	21	422.6	422.6	0	67.1	70.4	40.2	20.1	8.9	19.6	14.0
MENTOR HILLS DRIVE	5+06.42 – 5+86.18	79.76		* 224.3		*235.9	235.9	0	37.4	39.3	22.4	11.2	4.0	10.9	7.8
MENTOR HILLS DRIVE	5+86.19 – 8+09.54	223.35	20	496.3	20	496.3	0	496.3	0	0	49.6	24.8	0	24.1	17.2
MENTOR HILLS DRIVE	8+09.54 – 9+12.99	103.45		* 275.9		*290.2	290.2	0	46.0	48.4	27.6	13.8	5.1	13.4	9.6
MENTOR HILLS DRIVE	9+12.99 – 9+93.30	80.31	28	249.9	29	258.8	258.8	0	41.7	43.1	25.0	12.5	4.0	12.1	8.7
							1208	497	193	202	165	83	22	80	58

QUANTITIES CARRIED TO GENERAL SUMMARY

* AREA CALCULATED BY COMPUTER

CALCULATED JMZ | CHECKED WDB

PAVEMENT SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

54
393

COPYRIGHT – DATE: 08-09-01 11:03 , CT CONSULTANTS, INC. H:\CT\97125\SDSK\pavesbsum.dwg