DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 12" CONDUIT, TYPE B, AS PER PLAN (LIN. FT.)	603 12" CONDUIT, TYPE C, AS PER PLAN (LIN. FT.)			604 MANHOLE NO. 3, AS PER PLAN (EACH)	604 CATCH BASIN NO. 3A, AS PER PLAN (EACH)																
D-1	22+00	22+50	RT.		50			1																	
D-2	22+50	–	LT. & RT.	32					1																
TOTALS CARRIED TO THE DRAINAGE SUB-SUMMARY				32	50			1	1																

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 FENCE REMOVED (LIN. FT.)		608 CONCRETE STEPS, TYPE B (LIN. FT.)																			
R-1	24+10	25+00	RT.	90																					
ST-1	25+75	–	LT.			48																			
TOTALS CARRIED TO THE ROADWAY SUB-SUMMARY				90		48																			

CALCULATED J.C.C. CHECKED J.M.P.

ESTIMATED QUANTITIES – S.R. 615 STA. 22+00 TO STA. 26+00

LAK-IR90/SR615-9.26/1.51

COPYRIGHT – DATE: 07-09-01 09:06 , CT CONSULTANTS, INC. H:\CT\97125\SDSK\qsht706.dwg