DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 12" CONDUIT, TYPE B, AS PER PLAN (LIN. FT.)	603 12" CONDUIT, TYPE C, AS PER PLAN (LIN. FT.)			604 MANHOLE NO. 3, AS PER PLAN (EACH)	604 CATCH BASIN NO. 3A, AS PER PLAN (EACH)																
D-1	46+00	46+10	LT. & RT.	62	24/12*				2																
D-2	47+90	48+00	LT. & RT.	62	24/12*			1	2																
D-3	48+00	50+00	LT.		200																				
TOTALS CARRIED TO THE DRAINAGE SUB-SUMMARY				124	248/24*			1	4																

TOTALS CARRIED TO THE DRAINAGE SUB-SUMMARY

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 FENCE REMOVED (LIN. FT.)	202 STRUCTURE REMOVED (LIN. FT.)			690 MAIL BOX SUPPORT (EACH)																	
R-1	48+55	48+60	LT.	27																					
R-2	49+73	49+91	LT.		2																				
MB-1	47+30	-	LT.					1																	
MB-2	48+35	-	LT.					1																	
TOTALS CARRIED TO THE ROADWAY SUB-SUMMARY				27	2			2																	

*100% LOCAL PARTICIPATION

CALCULATED J.C.C. CHECKED J.M.P.

ESTIMATED QUANTITIES – S.R. 615 STA. 46+00 TO STA. 50+00

LAK-IR90/SR615-9.26/1.51

80 393

COPYRIGHT – DATE: 07-10-01 07:24 , CT CONSULTANTS, INC. H:\CT\97125\SDSK\qsht712.dwg