

SUPERELEVATION TABLE						
S.R. 615 (CURVE #1)			P.I. STATION 13+31.80		Dc = 6' 00' 00"	
LEFT SIDE		CENTERLINE CONTROL		RIGHT SIDE		REMARKS
EDGE PAV'T ELEV. 14' LEFT	RATE	STATION	PROFILE GRADE	RATE	EDGE PAV'T ELEV. 14' RIGHT	
769.11	0.0200	11+75	768.83	-0.0200	768.55	
769.25	0.0200	12+00	768.97	-0.0200	768.69	
769.39	0.0200	12+25	769.11	-0.0200	768.83	
769.53	0.0200	12+50	769.25	-0.0200	768.97	
769.67	0.0200	12+75	769.39	-0.0200	769.11	
769.81	0.0200	13+00	769.53	-0.0200	769.25	
769.95	0.0200	13+25	769.67	-0.0200	769.39	
770.09	0.0200	13+50	769.81	-0.0200	769.53	
770.23	0.0200	13+75	769.95	-0.0200	769.67	
770.37	0.0200	14+00	770.09	-0.0200	769.81	
770.51	0.0200	14+25	770.23	-0.0200	769.95	
770.65	0.0200	14+50	770.37	-0.0200	770.09	
770.79	0.0200	14+75	770.51	-0.0200	770.23	
770.89	0.0200	14+93.60	770.61	-0.0200	770.33	END FULL SUPER/START TRANSITION
770.90	0.0181	15+00	770.65	-0.0181	770.40	
770.91	0.0172	15+03	770.67	-0.0172	770.43	
770.92	0.0156	15+08.60	770.70	-0.0156	770.48	
770.93	0.0140	15+15.07	770.73	-0.0156	770.51	P.T.
770.94	0.0110	15+25	770.79	-0.0156	770.57	
770.98	0.0038	15+50	770.93	-0.0156	770.71	
771.01	0.0000	15+63.60	771.01	-0.0156	770.79	FLAT PAVEMENT LT.
771.02	-0.0032	15+75	771.07	-0.0156	770.85	
771.07	-0.0103	16+00	771.21	-0.0156	770.99	
771.09	-0.0156	16+18.60	771.31	-0.0156	771.09	END TRANSITION