

TRAFFIC CONTROL GENERAL SUMMARY

SHEET NUMBER								ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN
285-292	295-A	295-B	298	323	324	327							
	200							603	00400	200	LIN. FT.	4" CONDUIT, TYPE E	290
	3720		10491					625	23000	14211	LIN. FT.	NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	290
	720	5212		375				625	25400	6307	LIN. FT.	CONDUIT, 2", 713.04	290
	1200	6	2870					625	25500	4076	LIN. FT.	CONDUIT, 3", 713.04	290
				5				625	25600	5	LIN. FT.	CONDUIT, 4", 713.04	
		724	139					625	25920	863	LIN. FT.	CONDUIT, MISC.: 3" METAL	
								625	25920	67	LIN. FT.	CONDUIT, MISC.: 4" METAL	
	360	5497		378				625	29000	6235	LIN. FT.	TRENCH	290
		440						625	29601	440	LIN. FT.	TRENCH IN PAVED AREA, TYPE B, AS PER PLAN	285
		4		21				625	30700	25	EACH	PULL BOX, 713.06, 18"	
		2	30		4			625	31600	36	EACH	PULL BOX, MISC.: 713.081, 13"x24", AS PER PLAN	285/290
								625	31600	1	EACH	PULL BOX, MISC.: 713.081, 17"x30", AS PER PLAN	287
								625	32000	10	EACH	GROUND ROD	
						4		625	34001	2	EACH	POWER SERVICE, AS PER PLAN	290
	1640	5497		340				625	36000	7477	LIN. FT.	SPECIAL PLASTIC CAUTION TAPE	
					161			630	02100	161	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 2 POST	
					825			630	03100	825	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
					160			630	06400	159.5	LIN. FT.	GROUND MOUNTED SUPPORT, S4x7.7 BEAM	
					77			630	06500	77	LIN. FT.	GROUND MOUNTED SUPPORT, W6x9 BEAM	
								630	07600	85.3	LIN. FT.	GROUND MOUNTED SUPPORT, W10x12 BEAM	
					120			630	08004	120	LIN. FT.	ONE WAY SUPPORT, NO. 3 POST	
					18			630	09000	18	EACH	BREAKAWAY BEAM CONNECTION	
						20		630	09102	20	EACH	SURFACE PREPARATION, NEW SUPPORT SECTION	289
						20		630	09104	20	EACH	COATING, EPOXY PRIME COAT, SUPPORT SECTION	288
								630	09106	20	EACH	COATING, EPOXY INTERMEDIATE COAT, SUPPORT SECTION	288
						20		630	09108	20	EACH	COATING, URETHANE TOP COAT, SUPPORT SECTION	289
						1		630	20300	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 3, 15' ARM	318
						1		630	20400	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 4, 22' ARM	318
						1		630	20600	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 6, 26' ARM	319
								630	20800	4	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 8, 25' ARM	319/320
						2		630	21000	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 10, 30' ARM	319/320
						1		630	77000	1	EACH	OVERPASS STRUCTURE MOUNTED SIGN SUPPORT, TC-18.24	
					13			630	79500	13	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
					600			630	80102	600	SQ. FT.	SIGN, FLATSHEET, TYPE G	
								630	80204	1726	SQ. FT.	SIGN, EXTRUSHEET, TYPE G	
					327	1399		630	84500	18	EACH	GROUND MOUNTED BEAM SUPPORT FOUNDATION	
					18			630	84510	10	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
						30		630	84900	30	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
						5		630	85100	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
								630	86002	34	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
						34		630	97700	1	EACH	SIGNING, MISC.: SIGNAL AND OVERHEAD SIGN SUPPORT, AS PER PLAN	287
						24		630	97900	24	LIN. FT.	SIGNING, MISC.: GROUND MOUNTED SUPPORT, WOOD POST, 4X4	
								631	84000	4	EACH	SIGN SERVICE	
						4		631	84300	6	EACH	SIGN WIRED	
						4		631	85100	4	EACH	DISCONNECT SWITCH WITH ENCLOSURE, TYPE X	
						8		631	87202	8	EACH	BALLAST, TYPE CMRI-175-480, INTEGRAL	
						8		631	89200	8	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC-31.21 WITH 175 WATT LAMP	

CALCULATED
T.E.B.
CHECKED
I.M.H.

**S.R. 615
TRAFFIC CONTROL GENERAL SUMMARY**

LAK - IR90 / SR615-9.26 / 1.51

283
393