

ITEM	SHEET NUMBER																	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL
	2	3	16	19	41	42	43	44	45	51	52	53	54	55	369								
201																	201	11000	LUMP		ROADWAY		
202																	202	11004	10	EACH	STRUCTURE REMOVED		
202																	202	11005	1	EACH	STRUCTURE REMOVED, AS PER PLAN	17	
202																	202	22900	170	SQ.YD.	APPROACH SLAB REMOVED		
202																	202	23000	9256	SQ.YD.	PAVEMENT REMOVED		
202																	202	30000	1120	SQ.FT.	WALK REMOVED		
202																	202	35100	2948	LIN.FT.	PIPE REMOVED, 24" AND UNDER		
202																	202	35200	6	LIN.FT.	PIPE REMOVED, OVER 24"		
202																	202	38000	3330	LIN.FT.	GUARDRAIL REMOVED		
202																	202	58200	17	EACH	INLET REMOVED		
202																	202	75000	7718	LIN.FT.	FENCE REMOVED		
203																	203	12000	74,997	CU.YD.	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION		
203																	203	20000	157,661	CU.YD.	EMBANKMENT		
203																	203	45000	80	HOUR	PROOF ROLLING		
203																	203	50000	67,984	SQ.YD.	SUBGRADE COMPACTION		
203																	203	60001	65	STA.	LINEAR GRADING, AS PER PLAN	17	
604																	604	38500	9	EACH	MONUMENT ASSEMBLY		
606																	606	13000	6932	LIN.FT.	GUARDRAIL, TYPE 5		
606																	606	22010	12	EACH	ANCHOR ASSEMBLY, TYPE E-98		
606																	606	25000	17	EACH	ANCHOR ASSEMBLY, TYPE A		
606																	606	26500	13	EACH	ANCHOR ASSEMBLY, TYPE T		
606																	606	35000	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 1		
606																	606	35100	2	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 2		
607																	607	23000	6706	LIN.FT.	FENCE, TYPE CLT		
608																	608	10000	46,361	SQ.FT.	4" CONCRETE WALK		
608																	608	41000	48	LIN.FT.	CONCRETE STEPS, TYPE A		
608																	608	49000	12	EACH	CURB RAMP		
622																	622	24000	160	LIN.FT.	CONCRETE BARRIER, TYPE D		
622																	622	24001	185	LIN.FT.	CONCRETE BARRIER, TYPE D, AS PER PLAN	109/110	
626																	626	00100	122	EACH	BARRIER REFLECTOR, TYPE A		
626																	626	00200	4	EACH	BARRIER REFLECTOR, TYPE B		
626																	626	00400	3	EACH	BARRIER REFLECTOR, TYPE B2		
SPECIAL																	SPECIAL	690E50000	5	EACH	MAILBOX SUPPORT	16	

CALCULATED J.C.C. CHECKED J.M.P.  
 GENERAL SUMMARY  
 LAK-IR90/SR615-9.26/1.51  
 36  
 393

H:\CT\97125\505K\97125651.DWG PLOT: 20