

ITEM	SHEET NUMBER																ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL
	18	19	20	44	48	49	50	51	52	53	54	55	56									
DRAINAGE (CONTINUED)																						
604							14										604	36600	14	EACH	PRECAST REINFORCED CONCRETE OUTLET	
SPECIAL			1000														SPECIAL	604E50000	1000	POUND	MISCELLANEOUS METAL	18
605						11,988	14,248										605	11110	26,236	LIN.FT.	6" SHALLOW PIPE UNDERDRAIN W/FABRIC WRAP	
605			100				295										605	13410	395	LIN.FT.	6" UNCLASSIFIED PIPE UNDERDRAIN W/FABRIC WRAP	
605			100				474										605	31100	574	LIN.FT.	AGGREGATE DRAIN	
SANITARY																						
604																	604	34501	1	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	18
604			2														604	37000	2	EACH	INSPECTION WELL	
PAVEMENT																						
254											3851	497					254	01000	4348	SQ.YD.	PAVEMENT PLANING, BITUMINOUS	
301					200						608	193	332				301	46000	1335	CU.YD.	BITUMINOUS AGGREGATE BASE, PG64-22	
304					200				3678	7017	228	202	272				304	20001	11,597	CU.YD.	AGGREGATE BASE, AS PER PLAN	19
304					22,500												304	20001	22,500	CU.YD.	AGGREGATE BASE, AS PER PLAN, TYPE 1	19
305											12,940						305	14000	12,940	SQ.YD.	10" CONCRETE BASE	
407											1283	385	165				407	10000	1953	GAL.	TACK COAT	
407													83				407	14000	83	GAL.	TACK COAT FOR INTERMEDIATE COURSE	
408																	408	10000	360	GAL.	PRIME COAT	
411															22		411	10000	22	CU.YD.	STABILIZED CRUSHED AGGREGATE	
446											624	133	80				446	46050	837	CU.YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	
446											535	275	58				446	50001	968	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN	19
448																216	448	46060	216	CU.YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-22 (UNDER GUARDRAIL)	
448																121	448	48020	121	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS)	
451																	451	14000	48,281	SQ.YD.	9" REINFORCED CONCRETE PAVEMENT	
SPECIAL											20,682	27,599					SPECIAL	451E30000	82	LIN.FT.	PRESSURE RELIEF JOINT, TYPE A	
452																225	452	10000	225	SQ.YD.	6" PLAIN CONCRETE PAVEMENT	
452																34	452	12000	34	SQ.YD.	8" PLAIN CONCRETE PAVEMENT	
611																241	611	25000	241	SQ.YD.	REINFORCED CONCRETE APPROACH SLAB, (T=15"), AS PER PLAN	(39/41)
830																17,465	830	14000	17,465	LIN.FT.	CURB, TYPE 2-A	
830																192	830	26000	192	LIN.FT.	CURB, TYPE 6	

CALCULATED J.C.C. CHECKED J.M.P.
 GENERAL SUMMARY
 LAK-IR90/SR615-9.26/1.51
 39
 393

H:\CT\19725\95SK\97125651.DWG PLOT=20