

* COMPUTER CALCULATED AREA

SIDEWALK				608	608	608	608	608
				4" CONCRETE WALK	CURB RAMP, DESIGN A	CURB RAMP, DESIGN B	CURB RAMP, DESIGN C	CURB RAMP, DESIGN G
SHEET	REF.	STATION TO STATION		SQ. FT.	EACH	EACH	EACH	EACH
67	SW-1	24+93.00	26+00.00	535.0				
69	SW-1	26+00.00	26+62.00	336.0				1
69	SW-2	27+05.00	28+02.45	*640.0	1			1
69	SW-3	27+24.20	28+06.31	*380.0		1		
71	SW-1	31+94.10	34+00.00	1029.5				
71	SW-2	32+02.70	34+00.00	986.5				
73	SW-1	34+00.00	36+47.00	1235.0				1
73	SW-2	34+00.00	36+48.00	1240.0				1
73	SW-3	37+13.00	38+00.00	435.0				1
73	SW-4	37+04.00	38+00.00	480.0				1
75	SW-1	38+00.00	42+00.00	2000.0				
75	SW-2	38+00.00	42+00.00	2000.0				
77	SW-1	42+00.00	46+00.00	1940.0				
77	SW-2	42+00.00	46+00.00	1940.0				
79	SW-1	46+00.00	50+00.00	1820.0				
79	SW-2	46+00.00	50+00.00	2000.0				
81	SW-1	50+00.00	54+00.00	2000.0				
81	SW-2	50+00.00	54+00.00	2000.0				
83	SW-1	54+00.00	58+00.00	1935.0				
83	SW-2	54+00.00	58+00.00	1919.5				
85	SW-1	58+00.00	62+00.00	2000.0				
85	SW-2	58+00.00	62+00.00	2000.0				
87	SW-1	62+00.00	66+00.00	2000.0				
87	SW-2	62+00.00	66+00.00	2000.0				
89	SW-1	66+00.00	70+00.00	2000.0				
89	SW-2	66+00.00	70+00.00	2000.0				
91	SW-1	70+00.00	74+00.00	2000.0				
91	SW-2	70+00.00	74+00.00	2000.0				
93	SW-1	74+00.00	76+57.50	1288.0				1
93	SW-2	74+00.00	76+62.00	1310.0				1
93	SW-3	160+25 (S.R. 84)	77+76.50	*642.0			1	
93	SW-4	77+44.00	77+76.50	*269.0			1	
SUBTOTAL					1	1	2	8
TOTAL				46,361			12	

SIDEWALK SUB-SUMMARY TOTALS
CARRIED TO GENERAL SUMMARY

SIDEWALK SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

45
393

H:\CT\97125\SDSK\WKSBSUM.DWG -- PLOT SCALE = 1:1

CALCULATED
AED
CHECKED
J.M.P.