

FOR TYPICAL SECTIONS SEE SHEETS 6 THRU 15

PAVEMENT							203	304		451	SPECIAL		611		
STREET NAME	STATION TO STATION	LENGTH (FEET)	PAVEMENT AREA		BASE		SUBGRADE COMPACTION	6" AGGREGATE BASE AS PER PLAN		9" REINFORCED CONCRETE PAVEMENT	PRESSURE RELIEF JOINT TYPE A		T = 15" REINFORCED CONCRETE		
			AVE. WIDTH (FEET)	PMT AREA SQ. YDS.	AVE. WIDTH (FEET)	PMT AREA SQ. YDS.									
							SQ. YDS.	CU. YDS		SQ. YDS.	LIN. FT.		SQ. YDS.		
SR 615	11+75.00 - 16+18.60	443.6	29	1429.4	30.5	1503.3	1503.3	250.6		1429.4					
SR 615	16+18.60 - 19+89.88	371.28	29	1196.3	31	1278.9	1278.9	213.1		1196.3					
SR 615	19+89.88 - 22+75.36	285.48	29	919.9	30.5	967.5	967.5	161.2		919.9					
SR 615	22+75.36 - 24+25.36	150	35	583.3	37	616.7	616.7	102.7		583.3					
SR 615	24+25.36 - 25+82.90	157.54	41	717.7	43	752.7	752.7	125.7		717.7					
EXTRA AREA	25+82.90 - 27+78.85			*1640.0		*1787.8	1787.8	298.6		1640.0	41.0				
SR 615/RAMPS C AND D															
SR 615	27+78.85 - 28+03.85	25	41	113.9	42	116.7	113.9	19.5					120.5		
SR 615	31+97.29 - 32+22.29	25	41	113.9	42	116.7	113.9	19.5					120.5		
SR 615	32+22.29 - 35+97.79	375.50	41	1710.6	43	1794.1	1794.1	299.0		1710.6	41.0				
EXTRA AREA	35+97.79 - 37+69.54			*1585.4		*1726.2	1726.2	288.3		1585.4					
SR 615/RAMPS A AND B															
SR 615	37+69.54 + 40+00.00	230.46	51	1305.9	53	1357.2	1357.2	226.6		1305.9					
SR 615	40+00.00 - 41+60.00	160	57	1013.3	59	1048.9	1048.9	174.8		1013.3					
SR 615	41+60.00 - 44+00.00	240	63	1680.0	65	1733.3	1733.3	288.9		1680.0					
SR 615	44+00.00 - 46+88.00	288	54	1728.0	57	1824.0	1824.0	304.0		1728.0					
SR 615	46+88.00 - 47+38.00	50	63	350.0	65	361.1	361.1	60.2		350.0					
SR 615	47+38.00 - 48+22.00	84	54	504.0	57	532.0	532.0	88.7		504.0					
SR 615	48+22.00 - 48+72.00	50	63	350.0	65	361.1	361.1	60.2		350.0					
SR 615	48+72.00 - 49+59.00	87	54	522.0	57	551.0	551.0	91.8		522.0					
SR 615	49+59.00 - 50+09.00	50	63	350.0	65	361.1	361.1	60.2		350.0					
SR 615	50+09.00 - 55+25.00	516	54	3096.0	57	3268	3268	544.7		3096.0					
							22053	3678		20682	82		241		

QUANTITIES CARRIED TO GENERAL SUMMARY

* AREA CALCULATED BY COMPUTER

COPYRIGHT - DATE: 08-09-01 11:03 . CT CONSULTANTS, INC. H:\CT\97125\SDSK\pavesum.dwg

CALCULATED
JMZ
CHECKED
WDB

PAVEMENT SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

51
393