DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 12" CONDUIT, TYPE B, AS PER PLAN LIN. FT.	603 12" CONDUIT, TYPE C, AS PER PLAN LIN. FT.			604 MANHOLE NO. 3, AS PER PLAN EACH	604 CATCH BASIN NO. 3A, AS PER PLAN EACH																
D-1	33+15	–	LT. & RT.	40					2																
D-2	33+15	34+00	LT.		87			1																	
TOTALS CARRIED TO THE DRAINAGE SUB-SUMMARY				40	87			1	2																

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 GUARDRAIL REMOVED LIN. FT.		202 APPROACH SLAB REMOVED SQ. YDS.																			
R-1	32+05	36+55	LT.	450																					
R-2	32+10	36+00	RT.	390																					
R-3	31+97.29	32+22.29	LT. & RT.			85																			
TOTALS CARRIED TO THE ROADWAY SUB-SUMMARY				840		85																			

CALCULATED J.C.C. CHECKED J.M.P.

ESTIMATED QUANTITIES – S.R. 615 STA. 30+00 TO STA. 34+00

LAK-IR90/SR615-9.26/1.51

COPYRIGHT – DATE: 07-09-01 10:32 . CT CONSULTANTS, INC. H:\CT\97125\SDSK\qsht708.dwg