

TRAFFIC CONTROL GENERAL SUMMARY

SHEET NUMBER								ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN
285-292	295-A	295-B	298	323	324	327							
		320						603	00400	320	LIN. FT.	4" CONDUIT, TYPE E	
		6						625	00900	6	EACH	CONNECTOR KIT, TYPE VI	
		13						625	01500	13	EACH	CABLE SPLICING KIT	
		4255						625	24320	4255	LIN. FT.	1 1/2" DUCT CABLE WITH THREE NO. 4 QWG, 500 VOLT CABLES	
720	5212		375					625	25400	6307	LIN. FT.	CONDUIT, 2", 713.04	
	6	278						625	25500	284	LIN. FT.	CONDUIT, 3", 713.04	
			5					625	25600	5	LIN. FT.	CONDUIT, 4", 713.04	
	724							625	25920	724	LIN. FT.	CONDUIT, MISC.: 3" METAL	
	67							625	25920	67	LIN. FT.	CONDUIT, MISC.: 4" METAL	
360	5497	3496	378					625	29000	9731	LIN. FT.	TRENCH, 24" DEEP	
	440							625	29601	440	LIN. FT.	TRENCH IN PAVED AREA, TYPE B, AS PER PLAN	285
		16						625	30700	16	EACH	PULL BOX, 713.08, 18"	
2	30		4					625	31600	36	EACH	PULL BOX, MISC.: 713.081, 13"x24", AS PER PLAN	285/290
	1							625	31600	1	EACH	PULL BOX, MISC.: 713.081, 17"x30", AS PER PLAN	287
	6				4			625	32000	10	EACH	GROUND ROD	
		1						625	34000	1	EACH	POWER SERVICE	
360	5497	3496	340					SPECIAL	62536000	9693	LIN. FT.	SPECIAL - PLASTIC CAUTION TAPE	
				161				630	02100	161	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 2 POST	
				825				630	03100	825	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
				160				630	08400	159.5	LIN. FT.	GROUND MOUNTED SUPPORT, S4x7.7 BEAM	
				77				630	06500	77	LIN. FT.	GROUND MOUNTED SUPPORT, W6x9 BEAM	
				85				630	07600	85.3	LIN. FT.	GROUND MOUNTED SUPPORT, W10x12 BEAM	
				120				630	08004	120	LIN. FT.	ONE WAY SUPPORT, NO. 3 POST	
				18				630	09000	18	EACH	BREAKAWAY BEAM CONNECTION	
					20			630	09102	20	EACH	SIGNING, MISC.: SURFACE PREPARATION, NEW SUPPORT SECTION	289
					20			630	09104	20	EACH	SIGNING, MISC.: COATING, EPOXY PRIME COAT, SUPPORT SECTION	288
					20			630	09106	20	EACH	SIGNING, MISC.: COATING, EPOXY INTERMEDIATE COAT, SUPPORT SECTION	288
					20			630	09108	20	EACH	SIGNING, MISC.: COATING, URETHANE TOP COAT, SUPPORT SECTION	289
					1			630	20300	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 3, 15' ARM	318
					1			630	20400	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 4, 22' ARM	318
					1			630	20600	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 6, 26' ARM	319
					4			630	20800	4	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 8, 25' ARM	319/320
					2			630	21000	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 10, 30' ARM	319/320
					1			630	77000	1	EACH	OVERPASS STRUCTURE MOUNTED SIGN SUPPORT, TC-18.24	
				13				630	79500	13	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
				600				630	80102	600	SQ. FT.	SIGN, FLATSHEET, TYPE G	
				327	1399			630	80204	1726	SQ. FT.	SIGN, EXTRUSHEET, TYPE G	
				18				630	84500	18	EACH	GROUND MOUNTED BEAM SUPPORT FOUNDATION	
					10			630	84510	10	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
				30				630	84900	30	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
				5				630	85100	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
				34				630	86002	34	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					1			630	97700	1	EACH	SIGNING, MISC.: SIGNAL AND OVERHEAD SIGN SUPPORT, AS PER PLAN	287
				24				630	97900	24	LIN. FT.	SIGNING, MISC.: GROUND MOUNTED SUPPORT, WOOD POST, 4X4	
				4				631	08400	4	EACH	SIGN SERVICE	
				6				631	84300	6	EACH	SIGN WIRED	
				4				631	85100	4	EACH	DISCONNECT SWITCH WITH ENCLOSURE, TYPE X	
				8				631	87202	8	EACH	BALLAST, TYPE CMRI-175-480, INTEGRAL	
				8				631	89200	8	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC-31.21 WITH 175 WATT LAMP	

CALCULATED
T.E.B.

CHECKED
I.M.H.

**S.R. 615
TRAFFIC CONTROL GENERAL SUMMARY**

LAK - IR90 / SR615-9.26 / 1.51

283
393