



PB11: STA. 78+93, 36' LT (13" x 24")

PB10: STA. 79+91, 36' LT (13" x 24")

P1: STA. 77+46, 50' LT  
EX. SIGNAL SUPPORT

PB2: STA. 77+48, 37' LT  
EX. PULLBOX

PB3: STA. 77+81, 36' LT  
EX. PULLBOX

PB11: STA. 160+10, 33' RT (13" x 24")

PB5: STA. 160+33, 30' RT - EX. PULLBOX

PB4: STA. 76+60, 49' LT - EX. PULLBOX

P4: STA. 76+51, 45' LT  
EX. SIGNAL SUPPORT  
INSTALL PED. HEAD AND PUSHBUTTON

P5: EX. PED POLE  
(TO BE REMOVED)

PB6: STA. 76+32, 33' RT - EX. PULLBOX  
EX. PED POLE  
(TO BE REMOVED)

P2: STA. 76+58, 44.5' RT  
EX. SIGNAL SUPPORT  
INSTALL PED. HEADS AND PUSHBUTTONS

PB7: STA. 76+64, 46' RT - EX. PULLBOX

P3: STA. 77+47, 49' RT  
EX. SIGNAL SUPPORT W/  
EX. PED. HEADS AND PUSHBUTTONS

PB1: STA. 77+42, 50.5' RT  
EX. PULLBOX

EX. CONTROLLER:  
STA. 77+44, 52.5' RT

PB8: STA. 75+18, 35' RT (13" x 24")

PB9: STA. 74+02, 35' RT (13" x 24")

CONSTRUCT 2" CONDUIT ON EAST SIDE OF  
S.R. 615 TO NEW PB @ STA. 32+50±.  
PULL BOXES (13" x 24") SHALL BE PLACED  
AT MAXIMUM 250' INTERVALS. (SEE SHT.)