

ITEM	SHEET NUMBER																		100% LOCAL PARTICIPATION	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL										
	2	8	9	10	32	33	35	37	38	39	40	41	42	44	80	83																			
																		ROADWAY																	
201M																			201M	11000	LUMP		CLEARING AND GRUBBING												
202M					2														202M	11004	2	EACH	STRUCTURE REMOVED												
202M					8069						450	37						202M	23000	8556	SQ. M.	PAVEMENT REMOVED													
202M							2252										29	202M	30000	2252	SQ. M.	WALK REMOVED													
202M					1528												31	202M	32000	1528	METER	CURB REMOVED													
202M					37													202M	35101	37	METER	PIPE REMOVED, 600 mm AND UNDER, AS PER PLAN	9												
202M					21													202M	38800	21	EACH	GUARD POST REMOVED													
SPECIAL					11													SPECIAL	202M52990	11	EACH	PARKING BLOCK REMOVED	61, 63												
202M					2													202M	58001	2	EACH	MANHOLE REMOVED, AS PER PLAN	9												
202M					15													202M	58301	15	EACH	CATCH BASIN OR INLET REMOVED, AS PER PLAN	9												
202M					52													202M	75000	52	METER	FENCE REMOVED													
202M					2													202M	98100	2	EACH	REMOVAL MISC.: TRENCH DRAIN REMOVED	51												
203M					2400		6292				260	148					414	203M	12000	9100	CU. M.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION													
203M							447										229	203M	20000	447	CU. M.	EMBANKMENT													
203M																		203M	45000	40	HOUR	PROOF ROLLING													
203M										16004	1293						1293	203M	50000	17297	SQ. M.	SUBGRADE COMPACTION													
203M															0.17	0.13	0.30	203M	60000	0.30	KILOMETER	LINEAR GRADING													
SPECIAL					LUMP													SPECIAL	530M14000	LUMP		STRUCTURAL SURVEY AND MONITORING OF VIBRATIONS													
604M		11																604M	38500	11	EACH	MONUMENT ASSEMBLY													
604M		3															2	604M	39500	3	EACH	MONUMENT BOX ADJUSTED TO GRADE													
608M							2481										31	608M	10000	2481	SQ. M.	100mm CONCRETE WALK													
608M							777										777	608M	10001	777	SQ. M.	100mm CONCRETE WALK, AS PER PLAN	10												
608M							28											608M	49000	28	EACH	CURB RAMP													
608M							32											608M	52000	32	SQ. M.	CURB RAMP													
SPECIAL		100																SPECIAL	690M65010	100	M. TON	WORK INVOLVING SOLID WASTE	8												
																		EROSION CONTROL																	
660M							3757										1096	660M	30000	3757	SQ. M.	SODDING, UNSTAKED													
870M							188										55	870M	00301	188	CU. M.	TOPSOIL, AS PER PLAN	8												
870M		250					376										110	870M	20000	626	KILOGRAM	COMMERCIAL FERTILIZER													
870M							2115										617	870M	30000	2115	KILOGRAM	AGRICULTURAL LIME													
870M			14															870M	35000	14	CU. M.	WATER													
870M			800															870M	40000	800	SQ. M.	MOWING													
877M			800															877M	10000	800	SQ. M.	TEMPORARY SEEDING AND MULCHING													
877M			140								280						280	877M	30100	420	METER	TEMPORARY PERIMETER FILTER FABRIC FENCE													
877M			20								40						40	877M	30200	60	METER	TEMPORARY DITCH CHECK FILTER FABRIC FENCE													
877M			320								639							877M	30300	959	METER	TEMPORARY INLET PROTECTION FILTER FABRIC FENCE													
877M			50															877M	60000	50	CU. M.	SEDIMENT REMOVAL													
																		DRAINAGE																	
603M			50															603M	00901	50	METER	150mm CONDUIT, TYPE B, AS PER PLAN	9												
603M			50															603M	01100	50	METER	150mm CONDUIT, TYPE C													
603M			50															603M	01400	50	METER	150mm CONDUIT, TYPE E													
603M			50							183								603M	01500	233	METER	150mm CONDUIT, TYPE F													
603M			65							483							36	603M	04401	548	METER	300mm CONDUIT, TYPE B, AS PER PLAN	9												
603M			65							60							3	603M	04600	125	METER	300mm CONDUIT, TYPE C													
603M										3								603M	05901	3	METER	375mm CONDUIT, TYPE B, AS PER PLAN	9												
603M										166								603M	07401	166	METER	450mm CONDUIT, TYPE B, AS PER PLAN	9												
603M										3								603M	10401	3	METER	600mm CONDUIT, TYPE B, AS PER PLAN	9												
603M										10								603M	11901	10	METER	675mm CONDUIT, TYPE B, AS PER PLAN	9												
603M										5								603M	13401	5	METER	750mm CONDUIT, TYPE B, AS PER PLAN	9												
603M										94								603M	16401	94	METER	900mm CONDUIT, TYPE B, AS PER PLAN	9												

GENERAL SUMMARY

LAX - 640 - 2.865 (178)

H:\1998\98208\DWG\GENSUM.DWG