ITEM	SHEET NUMBER 8	9	32	43	100% LOCAL PARTICIPATION	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL
										WATER WORKS	
604				1		604	34500	1	EACH	MANHOLE, ADJUSTED TO GRADE	
SPECIAL				20		SPECIAL	638M40110	20	METER	150mm WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHENICAL JOINT FITTINGS	142
SPECIAL				3		SPECIAL	638M40206	3	METER	200mm WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHENICAL JOINT FITTINGS	142
SPECIAL				13		SPECIAL	638M40410	13	METER	300mm WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHENICAL JOINT FITTINGS	142
SPECIAL				4		SPECIAL	638M40510	4	METER	400mm WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHENICAL JOINT FITTINGS	142
638M				7		638M	43100	7	EACH	FIRE HYDRANT EXTENDED & ADJUSTED TO GRADE	
638M				29		638M	43800	29	EACH	VALVE BOX ADJUSTED TO GRADE	
638M				27		638M	44100	27	EACH	METER AND BOX RELOCATED	
										SANITARY	
603M		50				603M	00901	50	METER	150mm CONDUIT, TYPE B, AS PER PLAN, FOR SANITARY	9
603M		50				603M	01100	50	METER	150mm CONDUIT, TYPE C, FOR SANITARY	
603M			34		34	603M	01801	34	METER	200mm CONDUIT, TYPE B, AS PER PLAN, FOR SANITARY	9
604M		2				604M	31501	2	EACH	MANHOLE, NO.3, AS PER PLAN, WITH 706.11 JOINTS	
604M			16			604M	34501	16	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	9
604M		2	5			604M	35501	7	EACH	MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN	9
604M	20					604M	37000	20	EACH	INSPECTION WELL	
604M			2			604M	98000	2	EACH	DRAINAGE STRUCTURE, MISC.: CLEANOUT ASSEMBLY ADJUSTED TO GRADE	

CALCULATED JKZ
CHECKED VDB

GENERAL SUMMARY

LAK - 640 - 2865 (178)

H:\1998\98208\DWG\GENSUM.DWG