

FOR TYPICAL SECTIONS SEE SHEETS 3 THROUGH 7.



CALCULATED  
W.D.B.  
CHECKED  
P.S.L.

## SIDEWALK SUB-SUMMARY

STREET NAME	SHEET	REF.	STATION TO STATION	SIDE	LENGTH (METERS)	DEDUCT FOR DRIVEWAY (METERS)	TOTAL LENGTH (METERS)	WIDTH (METERS)	AREA CALCULATED BY COMPUTER	SIDEWALK AREA	202	608	608	608	608	608	608									
											WALK REMOVED	100mm CONCRETE WALK	CURB RAMP, DESIGN 'A'	CURB RAMP, DESIGN 'C'	CURB RAMP, DESIGN 'C'	CURB RAMP, DESIGN 'G'	100mm CONCRETE WALK, AS PER PLAN									
											SQ. METER	SQ. METER	EACH	EACH	SQ.METER	EACH	SQ. METER									
S.R. 640	47	SW-1	STA. 2+773.4 TO STA. 2+780.3	LT	6.9	-	-	3.0	21.7	-	21.0*	21.7*			23		4.1*									
S.R. 640	47	SW-2	STA. 2+826.0 TO STA. 2+850.0	LT	24.0	6.6	17.4	1.5	30.0	26.1	49.0	56.1		1			10.4*									
S.R. 640	47	SW-3	STA. 2+827.2 TO STA. 2+850.0	RT	22.8	-	22.8	1.5	30.0	34.2	47.1	64.2	1				13.7*									
S.R. 640	47	SW-4	STA. 2+774.3 TO STA. 2+782.2	RT	-	-	-	-	9.3	-	8.4*	9.3*			9											
S.R. 640	49	SW-1	STA. 2+850.0 TO STA. 2+894.3	LT	44.3	13.0	31.3	1.5	18.8	47.0	67.2	65.8	1				12.8*									
E. 354th ST.	49	SW-2	STA. 1+014.0 TO STA. 1+030.0	LT	16.0	-	16.0	1.5	-	24.0	24.0	24.0					9.6*									
E. 354th ST.	49	SW-3	STA. 1+015.0 TO STA. 1+030.0	RT	15.0	-	15.0	1.5	-	22.5	22.5	22.5					9*									
S.R. 640	49	SW-4	STA. 2+917.8 TO STA. 2+950.0	LT	32.2	7.0	25.2	1.5	30.3	37.8	41.6	61.8	1				15.1*									
S.R. 640	49	SW-5	STA. 2+850.0 TO STA. 2+950.0	RT	100.0	29.0	71.0	1.5	-	106.5	133.5	106.5					42.6*									
S.R. 640	51	SW-1	STA. 2+950.0 TO STA. 3+050.0	LT	100.0	25.0	75.0	1.5	-	112.5	107.5	112.5					45*									
S.R. 640	51	SW-2	STA. 2+950.0 TO STA. 2+986.1	RT	36.1	15.9	20.2	1.5	21.7	30.3	36.4	52.0	1				12.1*									
E. 355th ST.	51	SW-3	STA. 0+970.0 TO STA. 0+985.6	LT	15.6	-	15.6	1.5	-	23.4	23.4	23.4					9.4*									
E. 355th ST.	51	SW-4	STA. 0+970.0 TO STA. 0+985.4	RT	15.4	7.4	8.0	1.5	-	12.0	23.1	12.0					4.8*									
S.R. 640	51	SW-5	STA. 3+009.5 TO STA. 3+050.0	RT	40.5	-	40.5	1.5	17.4	60.8	63.0	78.2		1			24.3*									
S.R. 640	53	SW-1	STA. 3+050.0 TO STA. 3+095.5	LT	45.5	7.0	38.5	1.5	19.1	57.8	75.6	76.9	1				23.1*									
E. 357th ST.	53	SW-2	STA. 1+013.4 TO STA. 1+030.0	LT	16.6	-	16.6	1.5	-	24.9	24.9	24.9					10.0*									
E. 357th ST.	53	SW-3	STA. 1+013.4 TO STA. 1+030.0	RT	16.6	7.5	9.1	1.5	-	13.7	24.9	13.7					5.5*									
S.R. 640	53	SW-4	STA. 3+120.0 TO STA. 3+150.0	LT	30.0	-	30.0	1.5	20.0	45.0	51.8	65.0	1				18.0*									
S.R. 640	53	SW-5	STA. 3+050.0 TO STA. 3+111.6	RT	61.6	11.0	50.6	1.5	20.1	75.9	95.2	96.0		1			30.4*									
E. 357th ST.	53	SW-6	STA. 0+977.8 TO STA. 0+984.4	LT	6.6	-	6.6	1.5	-	9.9	9.9	9.9					4.0*									
E. 357th ST.	53	SW-7	STA. 0+970.0 TO STA. 0+984.2	RT	14.2	7.0	7.2	1.5	-	10.8	21.3	10.8					4.3*									
S.R. 640	53	SW-8	STA. 3+135.7 TO STA. 3+150.0	RT	14.3	-	14.3	1.5	19.7	21.5	29.2	41.2		1			8.6*									
S.R. 640	55	SW-1	STA. 3+150.0 TO STA. 3+220.0	LT	70.0	21.0	49.0	1.5	-	73.5	46.8	73.5					29.4*									
S.R. 640	55	SW-2	STA. 3+150.0 TO STA. 3+220.0	RT	70.0	14.0	56.0	1.5	-	84.0	79.8	84.0					33.6*									
S.R. 640	55	SW-3	STA. 3+212.0 TO STA. 3+220.0	RT	15.2	-	15.2	1.0	-	15.3	15.3															
S.R. 640	57	SW-1	STA. 3+220.0 TO STA. 3+227.5	LT	7.5	-	7.5	1.5	21.0	11.3	19.6	32.3		1			4.5*									
E. 359th ST.	57	SW-2	STA. 1+016.7 TO STA. 1+050.0	LT	33.0	7.5	25.5	1.5	-	38.3	49.5	38.3					15.3*									
E. 359th ST.	57	SW-3	STA. 1+016.4 TO STA. 1+050.0	RT	33.6	6.5	27.1	1.5	-	40.6	50.4	40.6					20.2*									
S.R. 640	57	SW-4	STA. 3+248.8 TO STA. 3+300.0	LT	51.2	14.0	37.2	1.5	21.5	55.8	12.6	77.3		1			22.3*									
S.R. 640	57	SW-5	STA. 3+220.0 TO STA. 3+228.4	RT	8.4	-	8.4	1.5	17.9	12.6	22.4	34.7	1				5.0*									
E. 359th ST.	57	SW-6	STA. 0+960.0 TO STA. 0+985.6	LT	25.6	5.9	19.7	1.5	-	29.6	35.9	29.6					11.8*									
E. 359th ST.	57	SW-7	STA. 0+960.0 TO STA. 0+984.8	RT	24.8	-	24.8	1.5	-	37.2	37.2	37.2					14.9*									
S.R. 640	57	SW-8	STA. 3+250.8 TO STA. 3+300.0	RT	49.2	7.0	42.2	1.5	18.3	63.3	79.3	81.6		1			25.3*									
SUB-TOTAL SHEET 34																										
SUB-TOTAL SHEET 34											1449.3	1577.5	7	7	32	-	499.1*									

SUB-TOTAL CARRIED TO SHEET 35

SIDEWALK SUB-SUMMARY

LAK-640-2.865 (1.78)

\* 100% LOCAL PARTICIPATION

H:\1998\98208\DWG\SWALKSUM.DWG PLOT METRIC 20-1