

FOR TYPICAL SECTIONS SEE SHEET 3-7
 ** AREA BY COMPUTER CALCULATION



CALCULATED
 M.D.B.
 CHECKED
 P.S.L.

PAVEMENT									203	254	301	301	304	305	407	407	408	448	448	252
									SUBGRADE COMPACTION	PAVEMENT PLANING, BITUMINOUS (32mm)	118mm BITUMINOUS AGGREGATE BASE PG64-22	220mm BITUMINOUS AGGREGATE BASE PG64-22	150mm AGGREGATE BASE, AS PER PLAN	230mm CONCRETE BASE	TACK COAT @ 0.45 LITERS PER SQ. M.	TACK COAT FOR INTERMEDIATE COURSE @ 0.23 LITERS PER SQ. M.	BITUMINOUS PRIME COAT 1.80 LITERS PER SQ. M.	32mm ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	45mm ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	FULL DEPTH PAVEMENT SAWING
STREET NAME	STATION TO STATION	RESURFACING LENGTH (METER)	RESURFACING AREA		BITUMINOUS AGGREGATE			SQ. M.	SQ. M.	CU. M.	CU. M.	CU. M.	SQ. M.	LITERS	LITERS	LITERS	CU. M.	CU. M.	METERS	
			AVE. WIDTH (METER)	PMT AREA SQ. M.	BASE LENGTH	AREA														
					LT. & RT. (METER)	AVE. WIDTH (METER)	PMT AREA SQ. M.													
S.R. 91 (S)	0+810.000 TO 0+825.000	15.00	9.086	134.42	15.00	3.323	49.85	52.10	134.42	-	10.97	7.82	-	82.92	11.47	88.11	5.60	2.24	17.90	
S.R. 91 (S)	0+825.000 TO 0+879.954	54.95	9.086	492.42	54.95	3.907	214.69	222.93	492.42	-	47.23	33.44	-	318.20	49.38	386.44	22.63	9.66	55.00	
S.R. 91 (S)	0+879.954 TO 0+974.789	94.835	10.493	995.10	94.835	3.907	370.52	384.75	995.10	-	81.51	57.71	-	614.53	314.09	666.94	43.70	61.45	94.83	
S.R. 91 (S)	0+974.789 TO 2+827.154 (S.R. 640)	-	-	-	23.671	-	64.46**	68.01	-	-	14.18	10.20	-	27.01	14.83	116.03	2.06	2.90	27.47	
S.R. 640	2+764.528 TO 2+827.154	62.626	-	2034.72**	-	-	-	-	2034.72	-	-	-	-	915.62	-	-	65.11	-	-	
S.R. 91 (N)	2+764.528 TO 1+025.305 (S.R. 640)	-	-	-	27.988	-	63.63**	68.14	-	-	14.00	10.22	-	28.63	14.64	114.53	2.04	2.86	32.10	
S.R. 91 (N)	1+025.305 TO 1+120.774	95.469	10.493	1001.76	95.469	3.907	373.00	387.32	1001.76	-	82.06	58.10	-	618.64	316.20	671.40	43.99	61.86	95.47	
S.R. 91 (N)	1+120.774 TO 1+135.000	14.226	10.342	147.13	14.226	3.907	55.58	57.71	147.13	-	12.23	8.66	-	25.01	46.62	100.04	6.49	2.50	14.23	
S.R. 91 (N)	1+135.000 TO 1+150.000	15.00	9.086	134.42	15.00	3.323	49.85	52.10	134.42	-	10.97	7.82	-	82.92	11.47	88.11	5.60	2.24	17.90	
100% LOCAL PARTICIPATION									1293.06*	4939.97*	-	273.15*	193.97*	-	2713.48*	778.70*	2231.60*	197.22*	145.80*	354.90*

QUANTITIES CARRIED TO GENERAL SUMMARY

* 100% LOCAL PARTICIPATION

H:\1998\98208\DWG\PAVESUMM.DWG PLOT METRIC 1:1

PAVEMENT SUB-SUMMARY

LAK-640-2.865 (1.78)