FOR ADDITIONAL DRIVEWAY DETAILS

SEE SHEET 138

metric units

STREET NAME	SHEET NUMBER	REFERENCE NUMBER	CENTERLINE STATION	SIDE	TYPE R or C	202 PAVEMENT REMOVED S.M.	PROPOSED DRIVEWAY DIMENSIONS: APRON AREA LENGTH x AVG WIDTH	DRIVEWAY AREA LENGTH x AVG WIDTH	DRIVEWAY EXTRA AREA	PROPOSED DRIVEWAY AREAS: TOTAL RIDGID AREA S.M.	TOTAL FLEXIBLE OR STONE AREA S.M.	203 EXCAVATION 152mm DEPTH NOT INCLUDING EMBANKMENT CONST. C.M.	203 EXCAVATION 201mm DEPTH NOT INCLUDING EMBANKMENT CONST. C.M.	203 EXCAVATION 203mm DEPTH NOT INCLUDING EMBANKMENT CONST. C.M.	203 EXCAVATION 276mm DEPTH NOT INCLUDING EMBANKMENT CONST. C.M.	252 FULL DEPTH PAVEMENT SAWING METERS	304 150mm AGGREGATE BASE, AS PER PLAN C.M.	304 200mm AGGREGATE BASE, AS PER PLAN C.M.	448 32mm ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22, (DRIVEWAYS) AS PER PLAN C.M.	448 44mm ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22, (DRIVEWAYS) AS PER PLAN C.M.	448 50mm ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22, (DRIVEWAYS) AS PER PLAN C.M.	408 BITUMINOUS PRIME COAT @ 1.8 liters/m LITER	452 150mm PLAIN CONCRETE PAVEMENT S.M.	452 200mm PLAIN CONCRETE PAVEMENT S.M.
S.R. 640	47	DR-1	2+842.2	LT	C		3.8x6.9	1.2x7.3	8.8	26.2	8.8			5.3	2.4	24.8		1.8	0.3	0.4		15.7		26.2
S.R. 640	49	DR-2	2+856.2	LT	C		4.0x6.6	1.2x7.2	8.6	26.4	8.6			5.4	2.4	14.8		1.8	0.3	0.4		15.5		26.5
S.R. 640	49	DR-3	2+858.6	RT	C		3.9x6.6			25.8				5.2		7.1								25.6
S.R. 640	49	DR-4	2+871.1	LT	C		4.0x7.0	1.6x6.8	10.9	28.0	10.9			5.7	3.0	11.4		2.2	0.4	0.5		19.5		28.0
S.R. 640	49	DR-5	2+903.8	RT	C	25.9	3.0x7.3	10x6.2	6.2	21.9	62.0			1.1	1.7	6.0		1.3	0.2	0.3		11.2		22.0
S.R. 640	49	DR-6	2+918.7	RT	C	25.1	3.0x7.1	0.5x5.6	2.8	21.3	2.8			2.2	0.8	5.0		0.6	0.1	0.2		5.1		21.2
S.R. 640	49	DR-7	2+927.8	RT	R		3.0x4.6	0.8x3.1	2.5	13.8	2.5	2.1	0.5			2.6		0.5					13.7	
S.R. 640	49	DR-8	2+940.7	RT	R		3.0x4.6	2.0x3.5	7.0	13.8	7.0	2.1	1.4			3.4		1.4					13.7	
S.R. 640	49	DR-9	2+942.0	LT	C	21.0	3.0x7.4	2.7x6.9	18.6	22.2	18.6			4.5	5.2	36.4		3.8	0.6	0.8		33.7		22.1
S.R. 640	51	DR-10	2+957.4	RT	C	33.6	2.9x5.9	2.0x4.8	9.6	17.1	9.6			1.5	2.7	6.8		2.0	0.3	0.4		17.3		17.1
S.R. 640	51	DR-11	2+961.8	LT	C	28.0	3.0x7.5	1.8x9.7	17.5	22.5	17.5			4.6	4.8	26.8		3.5	0.6	0.8		31.4		22.4
S.R. 640	51	DR-12	2+977.0	RT	C	49.4	3.0x10.5	3.0x9.5	28.5	31.5	28.5			1.9	7.9	9.4		5.7	0.9	1.3		51.3		31.4
S.R. 640	51	DR-13	2+987.4	LT	C	14.4	3.0x7.6	1.9x9.6	18.2	22.8	18.2			4.6	5.0	18.9		3.6	0.6	0.8		32.8		22.7
S.R. 640	51	DR-13A	3+007.0	LT	C		3.0x11.4	3.0x11.4	34.2	34.2	34.2			6.9	9.5	0.0		6.9	1.1	1.5		61.6		34.2
S.R. 640	51	DR-14	3+041.6	LT	C		3.0x11.3	2.4x14.1	33.8	33.9	33.8			6.9	9.4	29.7		6.8	1.1	1.5		60.9		34.0
S.R. 640	53	DR-15	3+066.2	RT	C		3.0x10.6	2.6x8.6	22.4	31.8	22.4			6.5	6.2	121.8		4.5	0.8	1.0		40.2		31.8
S.R. 640	53	DR-16	3+074.1	LT	C		3.0x7.4	2.4x9.1	21.8	22.2	21.8			4.6	6.0	67.5		4.4	0.7	1.0		39.5		22.3
S.R. 640	55	DR-17	3+156.2	LT	C	23.8	3.0x7.6	1.4x10.3	14.4	22.8	14.4			4.7	4.0	61.2		2.9	0.5	0.7		26.0		22.9
S.R. 640	55	DR-18	3+190.1	LT	C	19.2	3.0x7.6	0.6x6.5	3.9	22.8	3.9			4.7	1.1	20.5		0.8	0.1	0.2		7.1		22.9
S.R. 640	55	DR-19	3+194.1	RT	C	66.4	3.0x7.6	2.5x6.6	16.5	39.3						8.5								39.2
S.R. 640	55	DR-20	3+205.1	RT	C		3.0x7.6	1.0x6.5	6.5	22.8	6.5			4.6	1.8	13.1		1.3	0.2	0.3		11.7		22.7
S.R. 640	55	DR-21	3+206.2	LT	C	23.4	3.0x7.6	0.6x6.5	3.9	22.8	3.9			4.6	1.1	15.2		0.8	0.1	0.2		7.1		22.7
S.R. 640	57	DR-22	3+259.2	LT	C	48.6	3.0x7.6	2.0x7.4	14.8	22.8	14.8			4.7	4.1	60.8		3.0	0.5	0.7		26.7		22.8
S.R. 640	57	DR-23	3+280.6	LT	C	43.9	3.0x11.9	2.0x11.9	23.8	35.7	23.8			7.2	6.6	50.1		4.8	0.8	1.0		42.8		35.7
S.R. 640	57	DR-24	3+284.9	RT	C		3.0x11.9	3.0x12	36.1	35.7	36.1			7.2	10.0	93.4		7.2	1.2	1.6		65.0		35.7
S.R. 640	59	DR-25	3+326.1	RT	C	13.6	3.0x7.6	3.0x6.1	18.3	22.8	18.3			4.7	5.1	5.6		3.7	0.6	0.8		32.8		22.8
S.R. 640	59	DR-26	3+359.8	LT	C		3.0x11.5	3.0x11.5	34.5	34.5	34.5			7.0	9.5	64.2		6.9	1.1	1.5		61.9		34.4
S.R. 640	61	DR-27	3+384.4	RT	C		3.0x7.4	4.0x7.6	30.4	22.2	30.4			4.6	8.5	40.8		6.1	1.0	1.4		54.9		22.2
S.R. 640	61	DR-28	3+416.4	RT	C		3.0x7.6	1.0x6.9	6.9	22.8	6.9			4.7	1.9	41.6		1.4	0.3	0.4		12.5		22.8
S.R. 640	61	DR-29	3+458.2	LT	C		3.0x7.6	1.0x6.5	6.5	22.8	6.5			4.7	1.8	6.6		1.3	0.2	0.3		11.7		22.8
S.R. 640	63	DR-30	3+493.5	LT	C	12.9	3.0x7.6	1.0x6.7	6.7	22.8	6.7			4.7	1.9	46.9		1.4	0.2	0.3		12.1		22.8
												4.2	1.9	135	124.4	920.1		92.4	14.8	20.3		808	27.4	759.9
						TOTAL 450				SHEET TOTAL		260				920	93		36			808	28	760

R = RESIDENTIAL DRIVEWAY
C = COMMERCIAL DRIVEWAY

CALCULATED W.D.R. CHECKED P.S.L.

DRIVEWAY SUB-SUMMARY

LAK-640-2.865 (1.78)

H:\1998\98208\SDSK\DRIVSAMP.DWG PLOT METRIC 20:1