DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN	603 450mm CONDUIT, TYPE B AS PER PLAN	603 300mm CONDUIT, TYPE C		604 MANHOLE NO. 3 AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN	604 CATCH BASIN NO. 2-2B AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN
				METERS	METERS	METERS		EACH	EACH	EACH	EACH
D-1	2+850.000	2+881.000	RT		31.0			1			
D-2	2+881.000	2+883.500	RT		2.5						
D-3	2+881.000		RT	2.3					1		
D-4	2+911.401		RT								1
D-5	2+925.402		LT			4.0				1	
D-6	2+925.402		LT & RT	15.0					1		
D-7	2+925.299		RT								1
D-8	2+934.990		RT	2.5					1		
D-9	2+934.990		RT			4.0				1	
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				19.8	33.5	8.0		1	3	2	2

ROADWAY , SANITARY & WATERWORKS

REF. NO.	STATION FROM	STATION TO	SIDE	202 INLET OR CATCH BASIN REMOVED, AS PER PLAN	202 PAVEMENT REMOVED	202 CURB REMOVED			202 FENCE REMOVED	604 MANHOLE ADJUSTED TO GRADE		638 METER AND BOX RELOCATED	638 VALVE BOX ADJUSTED TO GRADE	638 FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE
				EACH	SQ. M.	METER			METER	EACH		EACH	EACH	EACH
R-1	2+922.900		RT	1										
R-2	2+925.000		LT	1										
R-5	2+894.000	2+896.800	LT						14					
S-1	2+906.335		LT							1				
	2+850.000	2+948.000	LT & RT		1075	187								
	2+948.000	2+950.000	LT & RT		22	4								
W-1	2+850.560		10.891 RT									1		
W-2	2+860.330		9.374 RT										1	
W-3	2+860.210		10.720 RT									1		
W-4	2+865.240		11.565 LT									1		
W-5	2+874.650		12.682 RT									1		
W-6	2+891.900		9.774 LT										1	
W-7	2+891.940		12.00 LT											1
W-8	2+921.600		8.232 RT									1		
W-9	2+924.950		3.291 LT										1	
W-10	2+931.510		8.383 RT									1		
W-11	2+943.400		9.421 RT									1		
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				2	1097	191			14	1		7	3	1

CALCULATED A.E.D. CHECKED W.D.B.

ESTIMATED QUANTITIES STA. 2+850 TO STA. 2+950

LAK - 640 - 2.865 (1.78)

H:\1998\98208\dwg\Quantsht04.DWG