DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN	603 300mm CONDUIT, TYPE C	603 900mm CONDUIT, TYPE B AS PER PLAN		604 MANHOLE NO. 3 AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN	604 CATCH BASIN NO. 2-2B AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN
				METERS	METERS	METERS		EACH	EACH	EACH	EACH
D-1	3+060.000		LT & RT	18.0						1	
D-2	3+092.500	3+092.565	LT		4.0					1	
D-3	3+092.565	3+095.000	LT & RT	16.0				1	1		
D-4	3+095.000	3+095.000	RT	1.5					1		
D-5	3+095.000		RT		4.0					1	
D-6	3+092.500	3+097.500	RT			5.0					
D-7	3+092.565	3+104.168	LT		15.0				1		
D-8	3+119.971		RT								1
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				35.5	23.0	5.0		1	3	3	1

ROADWAY , SANITARY & WATERWORKS

REF. NO.	STATION FROM	STATION TO	SIDE	202 INLET OR CATCH BASIN REMOVED, AS PER PLAN	202 PAVEMENT REMOVED	202 CURB REMOVED	202 STRUCTURE REMOVED	202 PIPE REMOVED, 600mm AND UNDER, AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN		638 METER AND BOX RELOCATED	638 VALVE BOX ADJUSTED TO GRADE	638 FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE
				EACH	SQ. M.	METER	EACH	METER	EACH		EACH	EACH	EACH
R-1	3+092.466		LT	1				12					
R-2	3+092.466		RT	1									
R-3	3+060.000		LT				1						
S-1	3+091.901		LT						1				
S-2	3+091.901		RT						1				
S-3	3+123.922		LT						1				
S-4	3+123.922		RT						1				
S-5	3+146.587		LT						1				
	3+050.000	3+150.000	LT & RT		1097	192							
W-1	3+069.230		7.870 RT									1	
W-2	3+094.440		4.540 RT									1	
W-3	3+094.420		6.590 RT										1
W-4	3+105.150		11.550 LT									1	
W-5	3+121.710		2.362 LT									1	
W-6	3+144.220		9.852 LT								1		
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				2	1097	192	1	12	5		1	4	1

CALCULATED A.E.D.
CHECKED W.D.B.

ESTIMATED QUANTITIES STA. 3+050 TO STA. 3+150

LAK - 640 - 2.865 (1.78)

H:\1998\98208\dwg\Quants108.DWG