## DRAINAGE

| REF. NO. | STATION FROM | STATION TO | SIDE | 603 300mm CONDUIT, TYPE B AS PER PLAN | | 604 CATCH BASIN NO. 3A AS PER PLAN |
|---|---|---|---|---|---|---|
| | | | | METERS | | EACH |
| D-1 | 3+165.000 | | LT & RT | 16.0 | | 1 |
| D-2 | 3+180.000 | | RT | 1.5 | | 1 |
| TOTALS CARRIED TO DRAINAGE SUB-SUMMARY | | | | 17.5 | | 2 |

## ROADWAY , SANITARY & WATERWORKS

| REF. NO. | STATION FROM | STATION TO | SIDE | 202 PAVEMENT REMOVED | 202 CURB REMOVED | 202 METAL POST REMOVED | 604 MANHOLE ADJUSTED TO GRADE | 638 METER AND BOX RELOCATED | 638 VALVE BOX ADJUSTED TO GRADE |
|---|---|---|---|---|---|---|---|---|---|
| | | | | SQ. M. | METER | EACH | EACH | EACH | EACH |
| R-1 | 3+212.12 | 3+215.03 | RT | | | 4 | | | |
| R-2 | 3+217.58 | 3+219.77 | RT | | | 2 | | | |
| R-3 | 3+190.72 | | RT | | 6 | | | | |
| R-4 | 3+197.69 | | RT | | 12.5 | | | | |
| | 3+150.000 | 3+220.000 | LT & RT | 768 | 140 | | | | |
| S-1 | 3+182.621 | | LT | | | | 1 | | |
| W-1 | 3+155.030 | | 3.120 LT | | | | | | 1 |
| W-2 | 3+173.260 | | 9.500 LT | | | | | 1 | |
| W-3 | 3+197.790 | | 10.970 LT | | | | | 1 | |
| TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES | | | | 768 | 158.5 | 6 | 1 | 2 | 1 |

CALCULATED A.E.D.
CHECKED W.D.B.

ESTIMATED QUANTITIES STA. 3+150 TO STA. 3+220

LAK - 640 - 2.865 (1.78)



H:\1998\98208\dwg\Quantsht10.DWG