DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN	603 450mm CONDUIT, TYPE B AS PER PLAN	603 900mm CONDUIT, TYPE B AS PER PLAN		604 MANHOLE NO. 3 W/ 1500mm BASE AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE AS PER PLAN
				METERS	METERS	METERS		EACH	EACH	EACH
D-1	3+380.000	3+450.484	RT			70.5		1		
D-2	3+422.000		LT & RT	16.0					1	
D-3	3+450.484		RT		2.0					
D-4	3+450.484	3+452.784	RT	2.5						
D-5	3+450.484	3+452.984	RT	2.5						
D-6	3+457.419	3+462.000	RT	5.0					1	1
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				26.0	2.0	70.5		1	2	1

ROADWAY , SANITARY & WATER WORKS

REF. NO.	STATION FROM	STATION TO	SIDE	202 PAVEMENT REMOVED	202 CURB REMOVED	202 METAL POST REMOVED	202 FENCE REMOVED			603 200mm CONDUIT, TYPE B FOR SANITARY	604 MANHOLE ADJUSTED TO GRADE	604 MANHOLE RECONSTRUCTED TO GRADE		638 METER AND BOX RELOCATED	638 VALVE BOX ADJUSTED TO GRADE	638 FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	SPECIAL PARKING BLOCK REMOVED AND STORED
				SQ. M.	METER	EACH	METER			METERS	EACH	EACH		EACH	EACH	EACH	EACH
S-1	3+446.334		RT								1						
S-2	3+457.276		RT								1						
S-3	3+463.837		LT									1					
S-4	3+473.000	3+480.000	RT							7.0*							
	3+380.000	3+459.480	LT & RT	872	146												
	3+459.480	3+480.000	LT & RT	242	41												
R-1	3+380	3+437	LT														8
R-2		3+403.8	LT			2											
R-3	NOT USED																
R-4	3+477.600	3+480.800	RT				5										
R-5	3+452.600	3+482.000	LT				33										
W-1	3+403.840	3+398	11.60 LT													1	
W-2	3+405.070		9.880 LT												1		
W-3	3+406.320		11.790 LT												1		
W-4	3+438.860		7.656 RT												1		
W-5	3+444.080		2.990 LT												1		
W-6	3+445.620		3.530 LT												1		
W-7	3+470.320		7.110 RT											1			
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				1114	187	2	38			7.0*	2	1		1	5	1	8

* 100% LOCAL PARTICIPATION

CALCULATED A.E.D. CHECKED W.D.B.

ESTIMATED QUANTITIES STA. 3+380 TO STA. 3+480

LAK - 640 - 2.865 (1.78)

H:\1998\98208\dwg\Quantsht16.DWG