DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN	603 300mm CONDUIT, TYPE C		604 CATCH BASIN NO. 3A AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN
				METERS	METERS		EACH	EACH
D-1	3+508.000		RT		2.0		1	
D-2	3+511.000	3+535.212	LT & RT	28.5			1	1
D-3	3+496.561		RT					1
D-4	3+497.330		RT					1
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				28.5	2.0		2	3

ROADWAY , SANITARY & WATER WORKS

REF. NO.	STATION FROM	STATION TO	SIDE	202 INLET OR CATCH BASIN REMOVED, AS PER PLAN	202 PAVEMENT REMOVED	202 CURB REMOVED		603 200mm CONDUIT, TYPE B FOR SANITARY, AS PER PLAN		604 MANHOLE ADJUSTED TO GRADE			638 METER AND BOX RELOCATED	638 VALVE BOX ADJUSTED TO GRADE	638 FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	638 300mm DUCTILE IRON PIPE, ANSI CLASS 53		SPECIAL PARKING BLOCK REMOVED AND STORED
				EACH	SQ. M.	METER		METER		EACH			EACH	EACH	EACH	METERS		EACH
R-1	3+508.198		RT	1														
R-2	3+498	3+511	LT															3
S-1	3+480.000	3+483.000	RT					3.0*										
S-2	3+525.910		LT							1								
	3+480.000	3+539.400	LT & RT		889	111												
W-1	3+487.490		7.900 LT										1					
W-2	3+499.430		7.760 RT										1					
W-3	3+510.820		8.315 RT										1					
W-4	3+518.950		10.160 LT										1					
W-5	3+526.480		9.450 RT										1					
W-6	3+527.990		5.260 LT											1				
W-7	3+532.810		4.820 LT											1				
W-8	3+537.150		12.010 LT												1			
W-9	3+537.810		9.640 LT										1					
W-10	3+538.220		9.410 RT										1					
W-11	3+512.000	3+528.000	LT.													10		
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				1	889	111		3.0*		1			7	2	1	10		3

* 100% LOCAL PARTICIPATION

CALCULATED A.E.D. CHECKED W.D.B.

ESTIMATED QUANTITIES STA. 3+480 TO END PROJECT

LAK - 640 - 2.865 (1.78)

H:\1998\98208\dwg\Quantsh118.DWG