DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN	603 675mm CONDUIT, TYPE B AS PER PLAN	603 300mm CONDUIT, TYPE C		604 MANHOLE NO. 3 AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN
	FROM	TO		METERS	METERS	METERS		EACH	EACH
D-1	0+980.000		LT & RT	7.5					2
D-2	0+980.000	0+982.000	RT			2.5		1	
D-3	0+979.500	0+984.500	RT		5.0				
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				7.5	5.0	2.5		1	2

WATER WORKS

REF. NO.	STATION FROM	STATION TO	SIDE	638 150mm DUCTILE IRON PIPE, ANSI CLASS 53
	FROM	TO		METERS
W-1	0+974.000	0+986.000	LT	4
TOTALS CARRIED TO WATERWORK SUB-SUMMARY				4

CALCULATED A.E.D. CHECKED

ESTIMATED QUANTITIES EAST 359TH STREET (SOUTH)

LAK - 640 - 2.865 (1.78)

H:\1998\98208\dwg\Quantsht25.DWG