ITEM	SHEET NUMBER 11	12	13	14	100% LOCAL PARTICIPATION	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL
										MAINTENANCE OF TRAFFIC	
410M	235					410M	12000	235	CU. M.	TRAFFIC COMPACTED SURFACE TYPE A OR B	
608M	1200					608M	21200	1200	SQ. M.	TEMPORARY BITUMINOUS WALK	
614M			250			614M	11100	250	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
614M			250			614M	11200	250	HOUR	LAW ENFORCEMENT OFFICER	
SPECIAL				1		SPECIAL	614M11300	1	EACH	TEMPORARY TRAFFIC SIGNAL	14
614M		16				614M	12460	16	EACH	WORK ZONE MARKING SIGN	
614M					4	614M	12470	4	EACH	WORK ZONE SPEED LIMIT SIGN	
SPECIAL	10	10				SPECIAL	614M12500	20	SQ. M.	REPLACEMENT SIGN	
SPECIAL	15					SPECIAL	614M12600	15	EACH	REPLACEMENT DRUM	
614M	250		5			614M	13001	255	CU. M.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	11
614M		2.12				614M	21100	2.12	KILOMETER	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
614M		0.16				614M	21200	0.16	KILOMETER	TEMPORARY CENTER LINE, CLASS I, 740.06, TYPE I	
614M		2.14				614M	22100	2.14	KILOMETER	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
614M		0.74				614M	22200	0.74	KILOMETER	TEMPORARY EDGE LINE, CLASS I, 740.06, TYPE I	
614M		27				614M	23200	27	METER	TEMPORARY CHANNELIZING LINE, CLASS I, 642 PAINT	
614M		197				614M	24400	197	METER	TEMPORARY DOTTED LINE, CLASS I, 740.06 TYPE I	
614M		39				614M	26200	39	METER	TEMPORARY STOP LINE, CLASS I, 642 PAINT	
614M		11				614M	26400	11	METER	TEMPORARY STOP LINE, CLASS I, 740.06, TYPE I	
614M		23				614M	30200	23	EACH	TEMPORARY LANE ARROW, CLASS I, 642 PAINT	
614M		4				614M	32700	4	SQ. M.	TEMPORARY ISLAND MARKING, CLASS I	
615M						615M	10001	LUMP		TEMPORARY ROAD, AS PER PLAN	11
615M	2990					615M	20000	2990	SQ. M.	TEMPORARY PAVEMENT, CLASS A	
616M	200					616M	10000	225	CU. M.	WATER	
616M	5		5			616M	20000	10	M.TON	CALCIUM CHLORIDE	
617M			10			617M	10100	10	CU. M.	COMPACTED AGGREGATE, TYPE A	
617M			25			617M	25000	25	CU. M.	WATER	
642M			2.00			642M	00300	2.00	KILOMETER	CENTERLINE, TYPE 1	
642M		152				642M	30000	152	METER	REMOVAL OF PAVEMENT MARKING	
										BUILDING DEMOLITION	
202M						202M	56000	LUMP		BUILDING DEMOLISHED,	
										PARCEL NO. 34-A-008-E-00-021,22 1 STORY BLOCK BUILDING	
										TRAFFIC CONTROL	
										FOR TRAFFIC CONTROL GENERAL SUMMARY SEE SHEET 147	
614M						614M	11000	LUMP		MAINTAINING TRAFFIC	
623M						623M	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
624M						624M	10000	LUMP		MOBILIZATION	
806M						806M	16010	10	MONTH	FIELD OFFICE, TYPE B	

CALCULATED JMZ
CHECKED VDB

GENERAL SUMMARY

LAK - 640 - 2805 (178)

H:\1998\98208\DWG\GENSUM.DWG