FOR TYPICAL SECTIONS SEE
SHEETS 3 THROUGH 7.

metric units

CALCULATED M.D.B. | CHECKED P.S.L.

SIDEWALK SUB-SUMMARY

STREET NAME	SHEET	REF.	STATION TO STATION	SIDE	LENGTH (METERS)	DEDUCT FOR DRIVEWAY (METERS)	TOTAL LENGTH (METERS)	WIDTH (METERS)	AREA CALCULATED BY COMPUTER	SIDEWALK AREA	202 WALK REMOVED SQ. METER	608 100mm CONCRETE WALK SQ. METER	608 CURB RAMP, DESIGN A EACH	608 CURB RAMP, DESIGN C EACH	608 CURB RAMP, DESIGN C SQ.METER	608 CURB RAMP, DESIGN G EACH	608 100mm CONCRETE WALK, AS PER PLAN SQ. METER
S.R. 640	47	SW-1	STA. 2+773.4 TO STA. 2+780.3	LT	6.9	–	–	3.0	21.7	–	21.0*	21.7*			23		4.1*
S.R. 640	47	SW-2	STA. 2+826.0 TO STA. 2+850.0	LT	24.0	6.6	17.4	1.5	30.0	26.1	49.0	56.1		1			10.4*
S.R. 640	47	SW-3	STA. 2+827.2 TO STA. 2+850.0	RT	22.8	–	22.8	1.5	30.0	34.2	47.1	64.2	1				13.7*
S.R. 640	47	SW-4	STA. 2+774.3 TO STA. 2+782.2	RT	–	–	–	–	9.3	–	8.4*	9.3*			9		
S.R. 640	49	SW-1	STA. 2+850.0 TO STA. 2+894.3	LT	44.3	13.0	31.3	1.5	18.8	47.0	67.2	65.8	1				12.8*
E. 354th ST.	49	SW-2	STA. 1+014.0 TO STA. 1+030.0	LT	16.0	–	16.0	1.5	–	24.0	24.0	24.0					9.6*
E. 354th ST.	49	SW-3	STA. 1+015.0 TO STA. 1+030.0	RT	15.0	–	15.0	1.5	–	22.5	22.5	22.5					9*
S.R. 640	49	SW-4	STA. 2+917.8 TO STA. 2+950.0	LT	32.2	7.0	25.2	1.5	30.3	37.8	41.6	61.8	1				15.1*
S.R. 640	49	SW-5	STA. 2+850.0 TO STA. 2+950.0	RT	100.0	29.0	71.0	1.5	–	106.5	133.5	106.5					42.6*
S.R. 640	51	SW-1	STA. 2+950.0 TO STA. 3+050.0	LT	100.0	25.0	75.0	1.5	–	112.5	107.5	112.5					45*
S.R. 640	51	SW-2	STA. 2+950.0 TO STA. 2+986.1	RT	36.1	15.9	20.2	1.5	21.7	30.3	36.4	52.0	1				12.1*
E. 355th ST.	51	SW-3	STA. 0+970.0 TO STA. 0+985.6	LT	15.6	–	15.6	1.5	–	23.4	23.4	23.4					9.4*
E. 355th ST.	51	SW-4	STA. 0+970.0 TO STA. 0+985.4	RT	15.4	7.4	8.0	1.5	–	12.0	23.1	12.0					4.8*
S.R. 640	51	SW-5	STA. 3+009.5 TO STA. 3+050.0	RT	40.5	–	40.5	1.5	17.4	60.8	63.0	78.2		1			24.3*
S.R. 640	53	SW-1	STA. 3+050.0 TO STA. 3+095.5	LT	45.5	7.0	38.5	1.5	19.1	57.8	75.6	76.9	1				23.1*
E. 357th ST.	53	SW-2	STA. 1+013.4 TO STA. 1+030.0	LT	16.6	–	16.6	1.5	–	24.9	24.9	24.9					10.0*
E. 357th ST.	53	SW-3	STA. 1+013.4 TO STA. 1+030.0	RT	16.6	7.5	9.1	1.5	–	13.7	24.9	13.7					5.5*
S.R. 640	53	SW-4	STA. 3+120.0 TO STA. 3+150.0	LT	30.0	–	30.0	1.5	20.0	45.0	51.8	65.0	1				18.0*
S.R. 640	53	SW-5	STA. 3+050.0 TO STA. 3+111.6	RT	61.6	11.0	50.6	1.5	20.1	75.9	95.2	96.0		1			30.4*
E. 357th ST.	53	SW-6	STA. 0+977.8 TO STA. 0+984.4	LT	6.6	–	6.6	1.5	–	9.9	9.9	9.9					4.0*
E. 357th ST.	53	SW-7	STA. 0+970.0 TO STA. 0+984.2	RT	14.2	7.0	7.2	1.5	–	10.8	21.3	10.8					4.3*
S.R. 640	53	SW-8	STA. 3+135.7 TO STA. 3+150.0	RT	14.3	–	14.3	1.5	19.7	21.5	29.2	41.2		1			8.6*
S.R. 640	55	SW-1	STA. 3+150.0 TO STA. 3+220.0	LT	70.0	21.0	49.0	1.5	–	73.5	46.8	73.5					29.4*
S.R. 640	55	SW-2	STA. 3+150.0 TO STA. 3+220.0	RT	70.0	14.0	56.0	1.5	–	84.0	79.8	84.0					33.6*
S.R. 640	55	SW-3	STA. 3+212.0 TO STA. 3+220.0	RT	15.2	–	15.2	1.0	–	15.3	15.3						
S.R. 640	57	SW-1	STA. 3+220.0 TO STA. 3+227.5	LT	7.5	–	7.5	1.5	21.0	11.3	19.6	32.3		1			4.5*
E. 359th ST.	57	SW-2	STA. 1+016.7 TO STA. 1+050.0	LT	33.0	7.5	25.5	1.5	–	38.3	49.5	38.3					15.3*
E. 359th ST.	57	SW-3	STA. 1+016.4 TO STA. 1+050.0	RT	33.6	6.5	27.1	1.5	–	40.6	50.4	40.6					20.2*
S.R. 640	57	SW-4	STA. 3+248.8 TO STA. 3+300.0	LT	51.2	14.0	37.2	1.5	21.5	55.8	12.6	77.3		1			22.3*
S.R. 640	57	SW-5	STA. 3+220.0 TO STA. 3+228.4	RT	8.4	–	8.4	1.5	17.9	12.6	22.4	34.7	1				5.0*
E. 359th ST.	57	SW-6	STA. 0+960.0 TO STA. 0+985.6	LT	25.6	5.9	19.7	1.5	–	29.6	35.9	29.6					11.8*
E. 359th ST.	57	SW-7	STA. 0+960.0 TO STA. 0+984.8	RT	24.8	–	24.8	1.5	–	37.2	37.2	37.2					14.9*
S.R. 640	57	SW-8	STA. 3+250.8 TO STA. 3+300.0	RT	49.2	7.0	42.2	1.5	18.3	63.3	79.3	81.6		1			25.3*
									SUB-TOTAL SHEET 34		1449.3	1577.5	7	7	32	–	499.1*

SUB-TOTAL CARRIED TO SHEET 35

* 100% LOCAL PARTICIPATION

SIDEWALK SUB-SUMMARY

LAK-640-2.865 (1.78)

H:\1998\98208\DWG\SWALKSUM.DWG PLOT METRIC 20:1