FOR TYPICAL SECTIONS SEE
SHEETS 3 THROUGH 7.

metric units

CALCULATED M.D.B. | CHECKED P.S.L.

SIDEWALK SUB-SUMMARY

STREET NAME	SHEET	REF.	STATION TO STATION	SIDE	LENGTH (METERS)	DEDUCT FOR DRIVEWAY (METERS)	TOTAL LENGTH (METERS)	WIDTH (METERS)	AREA CALCULATED BY COMPUTER	SIDEWALK AREA	202 WALK REMOVED SQ. METER	608 100mm CONCRETE WALK SQ. METER	608 CURB RAMP, DESIGN A EACH	608 CURB RAMP, DESIGN C EACH	608 CURB RAMP, DESIGN F EACH	608 CURB RAMP, DESIGN G EACH	608 CURB RAMP, DESIGN C SQ.METER	608 100mm CONCRETE WALK, AS PER PLAN SQ. METER
S.R. 640	59	SW-1	STA. 3+300.0 TO STA. 3+310.6	LT	10.6	–	10.6	1.5	31.6	15.9	25.9	47.5	1					6.4*
E. 360th ST.	59	SW-2	STA. 1+014.4 TO STA. 1+047.2	LT	32.8	–	32.8	1.5	–	49.2	49.2	49.2						19.7*
E. 360th ST.	59	SW-3	STA. 1+014.3 TO STA. 1+040.8	RT	26.5	–	26.5	1.5	–	39.8	39.8	39.8						15.9*
S.R. 640	59	SW-4	STA. 3+335.4 TO STA. 3+380.0	LT	44.6	–	44.6	1.5	33.8	66.9	75.6	100.7	1	1				26.8*
S.R. 640	59	SW-5	STA. 3+300.0 TO STA. 3+338.0	RT	38.0	7.0	31.0	1.5	40.0	46.5	58.8	86.5	1	1				18.6*
E. 361st ST.	59	SW-6	STA. 0+970.0 TO STA. 0+979.2	LT	9.2	–	9.2	1.5	–	13.8	13.8	13.8						5.5*
E. 361st ST.	59	SW-7	STA. 0+970.0 TO STA. 0+979.2	RT	9.2	–	9.2	1.5	–	13.8	13.8	13.8						5.5*
S.R. 640	59	SW-8	STA. 3+375.2 TO STA. 3+380.0	RT	4.8	–	4.8	1.5	39.8	7.2	22.4	47.0	1					2.9*
S.R. 640	61	SW-1	STA. 3+380.0 TO STA. 3+398.6	LT	18.6	10.6	8.0	1.5	18.3	12.0	36.4	30.3		1				4.8*
E. 362nd ST.	61	SW-2	STA. 1+015.0 TO STA. 1+049.3	LT	34.3	8.0	26.3	1.5	–	39.5	51.5	39.5						15.8*
S.R. 640	61	SW-3	STA. 3+416.6 TO STA. 3+480.0	LT	63.4	7.0	56.4	1.5	–	84.6	93.8	84.6				1		45.1*
S.R. 640	61	SW-4	STA. 3+380.0 TO STA. 3+436.2	RT	56.2	14.0	42.2	1.5	17.5	63.3	89.6	80.8		1				25.3*
E. 363rd ST.	61	SW-5	STA. 0+970.0 TO STA. 0+985.2	LT	15.2	8.0	7.2	1.5	–	10.8	22.8	10.8						4.3*
S.R. 640	61	SW-6	STA. 3+454.4 TO STA. 3+480.0	RT	25.6	–	25.6	1.5	–	38.4	40.6	38.4				1		15.4*
S.R. 640	63	SW-1	STA. 3+480.0 TO STA. 3+515.0	LT	35.0	7.0	28.0	1.5	27.0	42.0	37.8	65.0	1					16.8*
E. 364th ST.	63	SW-2	STA. 1+015.0 TO STA. 1+040.0	LT	25.0	8.0	17.0	1.5	–	25.5	35.0	25.5						10.2*
E. 364th ST.	63	SW-3	STA. 1+013.1 TO STA. 1+040.0	RT	26.9	8.0	18.9	1.5	–	28.4	37.7	28.4						11.3*
S.R. 640	63	SW-4	STA. 3+536.8 TO STA. 3+539.4	LT	2.6	–	2.6	1.5	15.5	3.9	3.7	19.4		1				1.6*
S.R. 640	63	SW-5	STA. 3+480.0 TO STA. 3+539.4	RT	59.4	16.2	43.2	1.9	–	82.1	54.0	82.1			2			25.9*

SUB-TOTAL SHT. 35	802.2	903.1	5	5	2	2	–	277.8*
SUB-TOTAL SHT. 34	1449.3	1577.5	7	7	–	–	32	499.1*
100% LOCAL PARTICIPATION	29.4*	31.0*						777*
SUBTOTAL			12	12	2	2		
TOTAL	2251.5	2480.6	28				32	777*

SUB-SUMMARY TOTALS CARRIED TO GENERAL SUMMARY

* 100% LOCAL PARTICIPATION

SIDEWALK SUB-SUMMARY

LAK-640-2.865 (1.78)

35
189

H:\1998\98208\DWG\SWALKSUM.DWG PLOT METRIC 20:1