metric units

WATER WORKS SUB-SUMMARY

SHEET	STREET NAME	MANHOLE ADJUSTED TO GRADE, AS PER PLAN		METER AND BOX RELOCATED	VALVE BOX ADJUSTED TO GRADE	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE			150mm WATERMAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	200mm WATERMAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	300mm WATERMAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	400mm WATERMAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS
		604		638	638	638			SPECIAL	SPECIAL	SPECIAL	SPECIAL
		EACH		EACH	EACH	EACH			METER	METER	METER	METER
48	S.R. 640			1	1							
50	S.R. 640	1		7	3	1						
52	S.R. 640			3	3	1						
54	S.R. 640			2	4	1						
56	S.R. 640			2	1							
58	S.R. 640			3	3	1						
60	S.R. 640			2	5	1						
62	S.R. 640			1	5	1						
64	S.R. 640			7	2	1					10	
90	E. 354th ST.				2				4			
92	E. 355th ST.								4			
96	E. 357th ST. (SOUTH)			1								
98	E. 359th ST. (NORTH)								4			
100	E. 359th ST. (SOUTH)								4			
102	E. 360st ST.								4			
106	E. 362nd ST.											4
108	E. 363rd ST.									3		
110	E. 364th ST.										3	
	TOTALS	1		27	29	7			20	3	13	4

SUB-SUMMARY TOTALS CARRIED TO GENERAL SUMMARY

CALCULATED J.M.Z. CHECKED W.D.B.

WATER WORKS SUB-SUMMARY

LAK-640-2.865 (1.78)

H:\1998\98208\DWG\WTRSUM.DWG PLOT METRIC 1:1