

H:\1998\98208\dwg\Quantsh04.DWG

REF. NO.	STATION		SIDE	DRAINAGE																		
				603	603	603		604	604	604	604											
				300mm CONDUIT, TYPE B AS PER PLAN	450mm CONDUIT, TYPE B AS PER PLAN	300mm CONDUIT, TYPE C		MANHOLE NO. 3 AS PER PLAN	CATCH BASIN NO. 3A AS PER PLAN	CATCH BASIN NO. 2-2B AS PER PLAN	MANHOLE ADJUSTED TO GRADE, AS PER PLAN											
FROM	TO		METERS	METERS	METERS		EACH	EACH	EACH	EACH												
D-1	2+850.000	2+881.000	RT		31.0			1														
D-2	2+881.000	2+883.500	RT		2.5																	
D-3	2+881.000		RT	2.3					1													
D-4	2+911.401		RT																			
D-5	2+925.402		LT			4.0				1												
D-6	2+925.402		LT & RT	15.0					1													
D-7	2+925.299		RT																			
D-8	2+934.990		RT	2.5					1													
D-9	2+934.990		RT			4.0					1											
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				19.8	33.5	8.0		1	3	2	2											

REF. NO.	STATION		SIDE	ROADWAY , SANITARY & WATERWORKS																			
				202	202	202			202	604		638	638	638									
				INLET OR CATCH BASIN REMOVED, AS PER PLAN	PAVEMENT REMOVED	CURB REMOVED			FENCE REMOVED	MANHOLE ADJUSTED TO GRADE		METER AND BOX RELOCATED	VALVE BOX ADJUSTED TO GRADE	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE									
FROM	TO		EACH	SQ. M.	METER			METER	EACH		EACH	EACH	EACH										
R-1	2+922.900		RT	1																			
R-2	2+925.000		LT	1																			
R-5	2+894.000	2+896.800	LT					14															
S-1	2+906.335		LT						1														
	2+850.000	2+948.000	LT & RT		1075	187																	
	2+948.000	2+950.000	LT & RT		22	4																	
W-1	2+850.560		10.891 RT									1											
W-2	2+860.330		9.374 RT										1										
W-3	2+860.210		10.720 RT									1											
W-4	2+865.240		11.565 LT									1											
W-5	2+874.650		12.682 RT									1											
W-6	2+891.900		9.774 LT										1										
W-7	2+891.940		12.00 LT											1									
W-8	2+921.600		8.232 RT									1			1								
W-9	2+924.950		3.291 LT										1		1								
W-10	2+931.510		8.383 RT									1											
W-11	2+943.400		9.421 RT									1											
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				2	1097	191			14	1		7	3	1									

CALCULATED  
A.E.D.  
CHECKED  
W.D.B.

ESTIMATED QUANTITIES STA. 2+850 TO STA. 2+950

LAK - 640 - 2.865 (1.78)

50  
189