

H:\1998\98208\dwg\Quantst16.DWG

		DRAINAGE																				
REF. NO.	STATION		SIDE	603	603	603		604	604	604												
	FROM	TO		300mm CONDUIT, TYPE B AS PER PLAN	450mm CONDUIT, TYPE B AS PER PLAN	900mm CONDUIT, TYPE B AS PER PLAN		MANHOLE NO. 3 W/ 1500mm BASE AS PER PLAN	CATCH BASIN NO. 3A AS PER PLAN	MANHOLE ADJUSTED TO GRADE AS PER PLAN												
			METERS	METERS	METERS		EACH	EACH	EACH													
D-1	3+380.000	3+450.484	RT			70.5	1															
D-2	3+422.000		LT & RT	16.0				1														
D-3	3+450.484		RT		2.0																	
D-4	3+450.484	3+452.784	RT	2.5																		
D-5	3+450.484	3+452.984	RT	2.5																		
D-6	3+457.419	3+462.000	RT	5.0					1	1												
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				26.0	2.0	70.5		1	2	1												

		ROADWAY , SANITARY & WATER WORKS																						
REF. NO.	STATION		SIDE	202	202	202	202			603	604	604	638	638	638	SPECIAL								
	FROM	TO		PAVEMENT REMOVED	CURB REMOVED	METAL POST REMOVED	FENCE REMOVED			200mm CONDUIT, TYPE B FOR SANITARY	MANHOLE ADJUSTED TO GRADE	MANHOLE RECONSTRUCTED TO GRADE		METER AND BOX RELOCATED	VALVE BOX ADJUSTED TO GRADE	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	PARKING BLOCK REMOVED AND STORED							
			SQ. M.	METER	EACH	METER			METERS	EACH	EACH		EACH	EACH	EACH	EACH								
S-1	3+446.334		RT																					
S-2	3+457.276		RT							1														
S-3	3+463.837		LT							1	1													
S-4	3+473.000	3+480.000	RT						7.0*															
	3+380.000	3+459.480	LT & RT	872	146																			
	3+459.480	3+480.000	LT & RT	242	41																			
R-1	3+380	3+437	LT													8								
R-2		3+403.8	LT			2																		
R-3	NOT USED																							
R-4	3+477.600	3+480.800	RT				5																	
R-5	3+452.600	3+482.000	LT				33																	
W-1	3+403.840	3+398	11.60 LT												1									
W-2	3+405.070		9.880 LT											1										
W-3	3+406.320		11.790 LT											1										
W-4	3+438.860		7.656 RT											1										
W-5	3+444.080		2.990 LT											1										
W-6	3+445.620		3.530 LT											1										
W-7	3+470.320		7.110 RT																					
TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES				1114	187	2	38		7.0*	2	1		1	5	1	8								

CALCULATED
A.E.D.
CHECKED
W.D.B.

ESTIMATED QUANTITIES STA. 3+380 TO STA. 3+480

LAK - 640 - 2.865 (1.78)

62
189

* 100% LOCAL PARTICIPATION