

DRAINAGE

REF. NO.	STATION		SIDE	603	603	604	604																		
				300mm CONDUIT, TYPE B AS PER PLAN	375mm CONDUIT, TYPE B AS PER PLAN	MANHOLE NO. 3 AS PER PLAN	CATCH BASIN NO. 3 AS PER PLAN																		
	FROM	TO		METERS	METERS	EACH	EACH																		
D-1	1+020.000		LT & RT	7.5																					
D-2	1+020.000	1+060.000	RT	40.0		1	2																		
D-3	1+030.000	1+062.500	RT		2.5																				
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				47.5	2.5	1	2																		

ROADWAY , SANITARY & WATER WORKS

REF. NO.	STATION		SIDE	202	604	638	830																		
				INLET OR CATCH BASIN REMOVED, AS PER PLAN	MANHOLE ADJUSTED TO GRADE	150mm DUCTILE IRON PIPE, ANSI CLASS 53	CURB, TYPE 7																		
FROM	TO	EACH	EACH	EACH	METER																				
R-1	1+039.386		LT	1																					
R-2	1+044.000		RT	1																					
C-1	1+018.000	1+025.000	LT				7.0																		
S-1	1+042.648		RT		1																				
W-1	1+014.000	1+026.000	LT																						
TOTALS CARRIED TO ROADWAY, SANITARY, WATERWORKS & CURB SUB-SUMMARIES				2	1	4	7.0																		

CALCULATED
A.E.D.
CHECKED

ESTIMATED QUANTITIES EAST 359TH STREET (NORTH)

LAK - 640 - 2.865 (1.78)

198
189

H:\1998\98208\dwg\Quant\sh125.DWG