DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 300mm CONDUIT, TYPE B AS PER PLAN		604 CATCH BASIN NO. 3A AS PER PLAN		604 MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN
				METERS		EACH		EACH
D–1	1+006.937	1+012.752	LT	6.0				1
D–2	1+012.752		LT & RT	9.5		2		
TOTALS CARRIED TO DRAINAGE SUB–SUMMARY				15.5		2		1

CURB AND WATER WORKS

REF. NO.	STATION FROM	STATION TO	SIDE	638 150mm DUCTILE IRON PIPE, ANSI CLASS 53		830 CURB, TYPE 7
				METERS		METERS
W–1	1+007.752	1+017.752	RT.	4		
C–1	1+015.000	1+025.000	LT.			10.0
TOTALS CARRIED TO CURB & WATERWORK SUB–SUMMARIES				4		10.0

CALCULATED A.E.D. CHECKED

ESTIMATED QUANTITIES EAST 360TH STREET

LAK – 640 – 2.865 (1.78)

H:\1998\98208\dwg\Quantsht28.DWG