## DRAINAGE

| REF. NO. | STATION FROM | STATION TO | SIDE | 603 300mm CONDUIT, TYPE B AS PER PLAN | 603 300mm CONDUIT, TYPE C | | 604 CATCH BASIN NO. 3A AS PER PLAN | 604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN |
|---|---|---|---|---|---|---|---|---|
| | | | | METERS | METERS | | EACH | EACH |
| D-1 | 1+016.178 | | LT & RT | 6.5 | | | 2 | |
| D-2 | 1+016.178 | 1+009.003 | RT | | 12.0 | | | |
| D-3 | 1+043.542 | | LT | | | | | 1 |
| TOTALS CARRIED TO DRAINAGE SUB-SUMMARY | | | | 6.5 | 12.0 | | 2 | 1 |

## ROADWAY , SANITARY & WATER WORKS

| REF. NO. | STATION FROM | STATION TO | SIDE | 202 INLET OR CATCH BASIN REMOVED, AS PER PLAN | | | 638 400mm DUCTILE IRON PIPE, ANSI CLASS 53 |
|---|---|---|---|---|---|---|---|
| | | | | EACH | | | EACH |
| R-1 | 1+047.316 | | RT | 1 | | | |
| W-1 | 1+011.178 | 1+021.178 | LT | | | | 4 |
| TOTALS CARRIED TO ROADWAY, SANITARY AND WATERWORKS SUB-SUMMARIES | | | | 1 | | | 4 |

CALCULATED A.E.D.
CHECKED

ESTIMATED QUANTITIES EAST 362ND STREET

LAK - 640 - 2.865 (1.78)



H:\1998\98208\dwg\Quantsht29.DWG