* 707.41 NON-PERFORATED, ASTM D-3034 SDR35, 707.33 OR 707.42

REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION FROM	STATION TO	SIDE	STORM 202 PIPE REMOVED 600 mm AND UNDER		202 CATCH BASIN REMOVED		603 150 mm CONDUIT, TYPE F (*)	603 300 mm CONDUIT, TYPE B, AS PER PLAN	603 300 mm CONDUIT, TYPE C, AS PER PLAN	603 375 mm CONDUIT, TYPE B, AS PER PLAN	603 450 mm CONDUIT, TYPE B, AS PER PLAN				604 CATCH BASIN NO.2-2B AS PER PLAN	604 CATCH BASIN NO. 3 AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN	604 MANHOLE NO. 3 AS PER PLAN	604 MANHOLE NO. 5 AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE	604 MANHOLE RECONSTRUCTED TO GRADE	605 150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP			
					METER		EACH	METER	METER	METER	METER	METER	METER				EACH	EACH	EACH	EACH	EACH	EACH	EACH	METER			
D1	73	3+816.6	3+822	L&R						17.3	7.6						1	1									
D2		3+822	3+829.3	L							15.1						1	1			1						
D3		3+879.7	3+880.49	R						7.1									1								
D4		3+879.7		R																			1				
R1		3+846.4		L	5		1																				
R2		3+867.6	3+871.2	R	16		1																				
R3		3+871.2	3+879.7	R	8.6		1																				
R4		3+879.7	3+894	R	14.5		1																				
R5		3+893.6		L			1																				
U1-U8		3+800	3+900	L&R					18															202			
D1	74	3+927	3+927.25	L							3.8							1			1						
D2		3+927.25		L&R						23.6								1									
D3		3+927.25	3+960	R						32.8									1								
D4		3+960.7		R																			1				
D5		3+979	3+980.6	L						9.5									1								
D6		3+980.6		L																		1					
R1		3+925.6		R			1																				
R2		3+945.6		R			1																				
R3		3+977.6	3+980.6	L	10		1																				
R4		3+977.6	3+984.8	L	12.5		1																				
R5		3+994.2		R			1																				
U1-U6		3+900	4+000	L&R					18															203.25			
D1	75	4+023	4+037.5	R						14.5									2								
D2		4+037.5	4+060	R						36.5										1							
D3		4+032.6	4+036.7	L						7.8			4.8						1	1							
D4		4+053.5		R																		1					
D5		4+060	4+060	L&R						15.2									1								
D6		4+060	4+100	R						5.2		40							1	1							
S1		4+048.3		℄																		1					
R1		4+050.9	4+053.7	R	4.6		1																				
U1-U10		4+000	4+100	L&R					24															216			
TOTALS CARRIED TO SHEET 58A					71.2		11		60	169.5	26.5	40	4.8				2	4	8	3	2	3	2	621.25			

CALCULATED

CHECKED

ESTIMATED QUANTITIES - STA. 3+800 TO 4+100

LAK-640-3.444