* 707.41 NON-PERFORATED, ASTM D-3034 SDR35, 707.33 OR 707.42

REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION FROM	STATION TO	SIDE	STORM 202 PIPE REMOVED 600 mm AND UNDER	STORM 202 MANHOLE REMOVED	STORM 202 CATCH BASIN REMOVED	STORM 202 INLET BASIN REMOVED	STORM 603 150 mm CONDUIT, TYPE F (*) AS PER PLAN	STORM 603 200 mm CONDUIT, TYPE B 707.44 PS 46 MIN., 707.41 NON PERFORATED OR 706.08, AS PER PLAN	STORM 603 300 mm CONDUIT TYPE B, AS PER PLAN	STORM 603 300 mm CONDUIT, TYPE B, 748.01, ANSI CLASS 53 AS PER PLAN	STORM 603 300 mm CONDUIT TYPE C, AS PER PLAN	STORM 603 525 mm CONDUIT TYPE B, AS PER PLAN	STORM 603 365 mm X 575 mm CONDUIT, TYPE B, AS PER PLAN 706.04 H.E. III	STORM 603 490 mm X 770 mm CONDUIT, TYPE B, AS PER PLAN 706.04 H.E. III	STORM 604 CATCH BASIN NO. 3 AS PER PLAN	STORM 604	STORM 604 CATCH BASIN NO. 3A AS PER PLAN	STORM 604 CATCH BASIN NO. 2-2B AS PER PLAN	STORM 604 MANHOLE NO. 3 AS PER PLAN	STORM 604 MANHOLE RECONSTRUCTED TO GRADE	STORM 605 150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP	SANITARY 603 300 mm CONDUIT TYPE B, AS PER PLAN	SANITARY 603 375 mm CONDUIT TYPE B, AS PER PLAN	SANITARY 604 MANHOLE NO. 3 AS PER PLAN	BENDS AND BRANCHES FOR INFORMATION ONLY 375 mm 30° BEND
					METER	EACH	EACH	EACH	METER	METER	METER	METER	METER	METER	METER	METER	EACH		EACH	EACH	EACH	EACH	METER	METER	METER	EACH	EACH
D1	83	4+500	4+540	R								7.8				40					1						
D2		4+528.5	4+540	L									12.3							1							
D3		4+539	4+540	R							2.3						1										
D4		4+540		L&R								17.1					1										
D5		4+549		R						3	7.5																
D6		4+540	4+600	R											60												
D7		4+540	4+569.06	L								29.1					1										
D8		4+569	4+570.09	R							3						1										
D9		4+569.06	4+600	L							7	31															
S1		4+500	4+525	R																					25	1	
S2		4+525	4+600	R																					75		
S3		4+582.5		L																		1					
R1		4+509		L&R	2		1																				
R2		4+509	4+521.5	L	29.5		1	1																			
R3		4+548	4+549.5	L&R	17		1																				
R4		4+548	4+549.5	R	2		1																				
R5		4+500	4+600	R	100	1																	178.9				
R6		4+586.5		L&R	17		1																				
R7		4+586.5		R	2.5		1																				
U1-U6		4+500	4+600	L&R					18																		
D1	84	4+600	4+602.17	L								2.2					1										
D2		4+607.8	4+609	R							2.4						1										
D3		4+600	4+619.25	R							2.4				19.3						1						
D4		4+649.5	4+665	R							17.4		11.4						1	1							
D5		4+619.25	4+665	R							5.5			45.8					1		1						
D6		4+665	4+672.5	R										7.5													
S1		4+600	4+668.5	R																					6.0	68.5	1
S2		4+668.5	4+672	R																					4.0	1	1
S3		4+689.5		L																		1					
R1		4+600	4+621.3	R	21.3	1																					
R2		4+621.3	4+672	R	50.7																						
R3		4+648	4+649.5	L&R	24		1																				
R4		4+649		R				1																			
U1-U6		4+600	4+700	L&R					12														182				
TOTALS CARRIED TO SHEET 58A					266.0	2	7	2	30	3	47.5	87.2	23.7	53.3	79.3	40	6		2	2	3	2	360.9	10.0	168.5	3	1

CALCULATED

CHECKED

ESTIMATED QUANTITIES - STA. 4+500 TO 4+700

LAK-640-3.444

85
214

94014-PG-085-MSG 03/19/02

94-014