REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION FROM	STATION TO	SIDE	STORM 602 CONCRETE MASONRY			STORM 603 525 mm CONDUIT, TYPE B, AS PER PLAN	900 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	900 mm CONDUIT, TYPE C, AS PER PLAN (62.5 D-LOAD)	900 mm CONDUIT, TYPE C, AS PER PLAN (75 D-LOAD)	900 mm CONDUIT, TYPE C, BORED OR JACKED, AS PER PLAN (150 D-LOAD)	1050 mm CONDUIT TYPE B, AS PER PLAN (87.5 D-LOAD)	1050 mm CONDUIT TYPE C, AS PER PLAN (87.5 D-LOAD)	1200 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	1200 mm CONDUIT, TYPE B, AS PER PLAN (75 D-LOAD)	1200 mm CONDUIT TYPE B, BORED OR JACKED, AS PER PLAN (150 D-LOAD)	1200 mm CONDUIT, TYPE C, AS PER PLAN (62.5 D-LOAD)	1500 mm CONDUIT, TYPE C, AS PER PLAN (87.5 D-LOAD)					STORM 604 MANHOLE NO. 3 AS PER PLAN: TYPE B	MANHOLE NO. 3 AS PER PLAN	JUNCTION CHAMBER AS PER PLAN	
					CONCRETE MASONRY			525 mm CONDUIT, TYPE B, AS PER PLAN	900 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	900 mm CONDUIT, TYPE C, AS PER PLAN (62.5 D-LOAD)	900 mm CONDUIT, TYPE C, AS PER PLAN (75 D-LOAD)	900 mm CONDUIT, TYPE C, BORED OR JACKED, AS PER PLAN (150 D-LOAD)	1050 mm CONDUIT TYPE B, AS PER PLAN (87.5 D-LOAD)	1050 mm CONDUIT TYPE C, AS PER PLAN (87.5 D-LOAD)	1200 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	1200 mm CONDUIT, TYPE B, AS PER PLAN (75 D-LOAD)	1200 mm CONDUIT TYPE B, BORED OR JACKED, AS PER PLAN (150 D-LOAD)	1200 mm CONDUIT, TYPE C, AS PER PLAN (62.5 D-LOAD)	1500 mm CONDUIT, TYPE C, AS PER PLAN (87.5 D-LOAD)					MANHOLE NO. 3 AS PER PLAN: TYPE B	MANHOLE NO. 3 AS PER PLAN	JUNCTION CHAMBER AS PER PLAN	
		FROM	TO		CU.METER			METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER					EACH	EACH	EACH	
D1	97	5+400	0+072.5	℄												36	16.5										
D2		0+072.5	0+096.5	℄											24									1			
D3		0+096.5	0+140	℄														40						1			
D1	98	0+140	0+173.98	℄														35									
D2		0+173.98		℄	1.07																						
D1	101	4+443.7		L															2.4							1	
D2		4+443.7	4+438.5	L										7.3					2.4								
D3		4+438.5		L&℄									30.7												1		
D4		4+438.5		℄&R				2.4	14.3																1		
D5		4+438.5	4+452	R						19.2															1		
D6		4+452	4+460	R							8														1		
D1	102	4+460	4+470	R							5.1																
D2		4+470	4+577	R								120.3															
D3		4+577	4+600								14.5														1		
D1	103	4+600	4+740	R						140															1		
D1	104	4+740	4+801.5	R						62.6																	
TOTALS CARRIED TO 58A SUMMARY					1.07			2.4	14.3	221.8	27.6	120.3	30.7	7.3	24	36	16.5	75	4.8					2	6	1	

CALCULATED

CHECKED

ESTIMATED QUANTITIES OUTLET CHANNEL AND RELIEF SEWER

LAK-640-2.14

105
214

94014-PG-105-MSQ\11-24-00

94-014